REGULAR FLOW SILTSACK (*)

(FOR AREAS OF LOW TO MODERATE PRECIPITATION AND RUN-OFF)

PROPERTIES	TEST METHOD	UNITS
GRAB TENSILE STRENGTH GRAB TENSILE ELONGATION PUNCTURE MULLEN BURST TRAPEZOID TEAR UV RESISTANCE APPARENT OPENING SIZE FLOW RATE	ASTM D-4632 ASTM D-4632 ASTM D-4833 ASTM D-3786 ASTM D-4533 ASTM D-4751 ASTM D-4491 ASTM D-4491	300 LBS 20 % 120 LBS 800 PSI 120 LBS 80 % 40 US SIEVE 40 GAL/MIN/SQ
PERMITTIVITY	ASIM D-TTSI	0.55 SEC -1

HI-FLOW SILTSACK ®

(FOR AREAS OF MODERATE TO HEAVY PRECIPITATION AND RUN-OFF)

PROPERTIES	TEST METHOD	UNITS
GRAB TENSILE STRENGTH GRAB TENSILE ELONGATION PUNCTURE MULLEN BURST TRAPEZOID TEAR UV RESISTANCE APPARENT OPENING SIZE FLOW RATE PERMITTIVITY	ASTM D-4632 ASTM D-4632 ASTM D-4833 ASTM D-3786 ASTM D-4533 ASTM D-4535 ASTM D-4751 ASTM D-4491 ASTM D-4491	265 LBS 20 % 135 LBS 420 PSI 45 LBS 90 % 20 US SIEVE 200 GAL/MIN/SQ F 1.5 SEC -1

OIL-ABSORBANT SILTSACK®

(FOR AREAS WHERE THERE IS A CONCERN FOR OIL RUN-OFF OR SPILLS)

DEPENDING ON YOUR PARTICULAR APPLICATION, THE SILTSACK CAM BE MADE FROM EITHER ONE OF THE ABOVE FABRICS WITH AN OIL—ABSORBANT PILLOW INSERT OR, MADE COMPLETELY FROM AN OIL—ABSORBANT SILTSACK®, WITH A WOVEN PILLOW INSERT.

DETAIL OF INLET SEDIMENT CONTROL DEVICE
WITH CURB DEFLECTOR

N.T.S.

FILTER FABRIC
(IN CONFORMANCE WITH SECTION 985 FDOT SPEC.) POST OPTIONS: WOOD 2.5" MIN. DIA. WOOD 2"x4" TOWARD FLOW) 6' MAX. OAK 1.5"x1.5" STEEL 1.33 Lbs/Ft. Min. FILTER FABRIC ATTACH
SECURELY TO UPSTREAM
SIDE OF POST OR OF
USED THE WIRE MESH APPROXIMATELY 8 INCHES OF FILTER FABRIC
MATERIAL MUST EXTEND INTO A TRENCH AND BE ANCHORED WITH ELEVATION SECTION COMPACTED BACKFILL MATERIAL TYPE III SILT FENCE DETAIL

PRINCIPLE POST
POSITION (CANTED 20°
TOWARD FLOW)

ATTACHING TWO SILT-FENCES
WHEN TRENCHING IS USED

PLACE THE END POST
OF ONE FENCE INSIDE
THE END POST OF THE

consultants inc.

EB 2389
720 S.W. 2nd Ave, South Tower, Suite 300
GAINESVILLE, FLORIDA 32601
TEL. (352) 373-3541
www.edafl.com mail@edafl.com

SCALES: AS SHOWN

No. Date Comment

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DOUGLAS
J. MCGRATH, P.E. ON THE DATE ADJACENT TO THE SEAL.

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DOUGLAS J. MCGRATH, P.E. ON THE DATE ADJACENT TO THE SEAL.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

Professioned Engineer of Record:

SOUCHNSE

No 93515

ROSE

OF FLORIDA

Engineer Certificate No.

Project No:

22-013

Project phase:

CONSTRUCTION PLANS

Project title:

TUCKER DAVIS
TECHNOLOGIES SITE PLAN
CITY OF ALACHUA,
FLORIDA

Sheet title:

EROSION CONTROL DETAILS

Designed: DJM Sharper Sharper

TREE TRUNK

1" x 4" WOOD
BRACING

ORANGE-MESH
CONSTRUCTION FENCING

BRACING POLE

BURY POST

ELEVATION

N.T.S.

NOTES:

- 1. TREE BARRICADES WILL BE BUILT BEFORE ANY SITE WORK IS UNDERTAKEN AND WILL REMAIN IN PLACE UNTIL THE LANDSCAPING IS
- 2. EACH BARRICADE MUST BE AT LEAST 3 FEET TALL, WITH CORNER POSTS OF 2" X 4" WOOD INSERTED AT LEAST ONE AND A HALF (1-1/2) FEET DEEP. THE TWO ROWS OF SIDE SLATS MUST BE 1" X 4" AND BE MARKED WITH PLASTIC RIBBONS OR MESH FENCING FOR VISIBILITY.
- 3. NO GRADING WITHIN FENCING. ANY ROOTS GREATER THAN 1" IN DIAMETER THAT ARE DAMAGED OR EXPOSED SHALL BE CLEANLY CUT AND COVERED OVER WITH SOIL.
- 4. NO CONSTRUCTION MATERIALS OR EQUIPMENT SHALL BE PERMITTED WITHIN CONSTRUCTION FENCING OR BEYOND THE CONSTRUCTION LIMITS.
- 5. THE AREA ENCLOSED MUST BE AT OR OUTSIDE THE DRIPLINE FOR ALL HERITAGE AND CHAMPION TREES AND ALL REGULATED PINE AND PALM TREES, OR EQUAL TO 2/3 OF THE DRIPLINE OF THE TREE CANOPY FOR ALL OTHER REGULATED SPECIES, OR AT THE TREE ROOT PLATE WHERE ALLOWED BY CONSTRUCTION LIMITS.

TREE BARRICADE FENCING DETAIL