SAN FELASCO TECH CITY


CITY OF ALACHUA, FLORIDA

	DEVELOPMENT INFORMATION				
1.	PROJECT OWNER:	TOM R. & ASSOCIATES, LLC 11 SE 2ND AVENUE GAINESVILLE, FLORIDA 32601			
2.	NAME OF PROJECT:	SAN FELASCO TECH CITY			
3.	PROJECT DESCRIPTION:	CONSTRUCTION OF TWO 30,100 S.F. BUILDINGS FOR COMMERCIAL AND OFFICE USE AND ASSOCIATED INFRASTRUCTURE IMPROVEMENTS			
4.	PROJECT ADDRESS:	12000 BLOCK OF NW US HWY 441			
5.	TAX PARCEL NUMBER:	05962-002-000 (PORTION OF)			
6.	SECTION/TOWNSHIP/RANGE:	SECTION 20, TOWNSHIP 08 SOUTH, RANGE 19 EAST			
7.	ZONING:	COMMERCIAL INTENSIVE, LIGHT AND INDUSTRIAL WAREHOUSE			
8.	FUTURE LAND USE DESIGNATION:	COMMERCIAL, INDUSTRIAL			
9.	A PORTION OF THIS SITE IS LOCATED IN FLOOD PLAIN				
10.	IRRIGATION SYSTEM IS PROVIDED FOR LANDSCAPED AREAS				
11.	THE PROJECT SITE WILL MEET ALL	NPDES CRITERIA DURING AND AFTER CONSTRUCTION.			

	PROJECT AREA IMPERVIOUS AREA CALCULATIONS						
#	DESCRIPTION SQUARE FOOTAGE (S.F.) ACREAGE (AC.) PERCENTAGE (%)						
1.	TOTAL PROJECT AREA:	576,083	13.23	100			
2.	PROPOSED BUILDING COVERAGE:	60,200	1.38	10.4			
3.	PAVEMENT AND SIDEWALK AREA:	119,166	2.74	20.7			
4.	TOTAL IMPERVIOUS AREA:	179,366	4.12	31.1			
5.	OPEN AREA:	396,717	9.11	68.9			
6.	FLOOR TO AREA RATIO:	59,500 BUILDING AREA	SF: 576,083 PROJECT	AREA SF=0.10			

TOTAL SITE IMPERVIOUS AREA CALCULATIONS						
#	DESCRIPTION	SQUARE FOOTAGE	ACREAGE	PERCENTAGE		
1.	TOTAL SITE AREA:	2,411,418 S.F.	55.36 Ac.	100%		
2.	PROPOSED BUILDING COVERAGE:	60,200 S.F.	1.38 Ac.	2.50%		
3.	PAVEMENT AND SIDEWALK AREA:	119,166 S.F.	2.74 Ac.	4.95%		
4.	TOTAL IMPERVIOUS AREA:	179,366 S.F.	4.12 Ac.	7.44%		
5.	OPEN AREA:	2,232,052 S.F.	51.24 Ac.	92.56%		

	PARKING CALCULATIONS							
#	DESCRIPTION	CRITERIA	REQUIRED (MIN.)	PROVIDED				
1.	1. VEHICULAR PARKING							
	BUILDING A	1 PARKING SPACE PER 330 SF OFFICE X 30,000 S.F.	91	SEE TOTAL BELOW				
	BUILDING B 1 PARKING SPACE PER 305 SF RETAIL X 3,000 S.F.		10	SEE TOTAL BELOW				
		1 PARKING SPACE PER 330 SF OFFICE X 15,000 S.F.	45	SEE TOTAL BELOW				
		1 PARKING SPACE PER 1,000 SF ASSEMBLY X 12,000 S.F.	12	SEE TOTAL BELOW				
		TOTAL	158	160 INCLUDING 6 HANDICAP SPACES				
2.	BICYCLE PARKING	10% OF REQUIRED NUMBER OF VEHICLE PARKING	158 SPACES X 0.10 = 16 SPACES	16 SPACES 8 RACKS				
3.	MOTORCYCLE PARKING	N/A	N/A	N/A				



LEGEND:

ZONING:	
ILW	_

- LIGHT AND INDUSTRIAL WAREHOUSE
- COMMERCIAL INTENSIVE

H — BUSINESS HIGHWAY
CC — COMMUNITY COMMERCIAL DISTRICT
IP — INDUSTRIAL SERVICES AND MANUFACTURING

FUTURE LAND USE: C — COMMERCIAL

CC — COMMUNITY COMMERCIAL
I — INDUSTRIAL
REC — RURAL EMPLOYMENT CENTER

TRIP GENERATION

PROPOSED ITE LAND USE 710 GENERAL OFFICE BUILDING							
45,000 S.F.				TRIP DIS	TRIBUTION	PROJE	CT TRIPS
PERIOD	RATE	PER 1000 SF	TRIPS	ENTER	EXIT	IN	OUT
AM PK HR	1.16	45.00	52.20	86%	14%	44.89	7.31
PM PK HR	1.15	45.00	51.75	16%	84%	8.28	43.47
AVG DAILY	9.74	45.00	438.30	50%	50%	219.15	219.15

 ITE LAND USE 820 SHOPPING CENTER							
3,000 S.F.				TRIP DISTRI	BUTION	PROJECT	TRIPS
PERIOD	RATE	PER 1000 SF	TRIPS	ENTER	EXIT	IN	OUT
AM PK HR	0.94	3.00	2.82	62%	38%	1.75	1.07
PM PK HR	3.81	3.00	11.43	48%	52%	5.49	5.94
AVG DAILY	37.75	3.00	113.25	50%	50%	56.63	56.63

ITE LAND USE 110 GENERAL LIGHT INDUSTRIAL							
12,000 S.F.				TRIP DI	STRIBUTION	PROJEC	T TRIPS
PERIOD	RATE	PER 1000 SF	TRIPS	ENTER	EXIT	IN	OUT
AM PK HR	0.70	12.00	8.40	88%	12%	7.39	1.01
PM PK HR	0.63	12.00	7.56	13%	87%	0.98	6.58
AVG DAILY	4.96	12.00	59.52	50%	50%	29.76	29.76

SUMMARY			
	AM PK HR	PM PK HR	AVG DAILY
OFFICE	52.20	51.75	438.30
RETAIL	2.82	11.43	113.25
GENERAL LIGHT INDUSTRIAL	8.40	7.56	59.52
OVERALL NET	63.42	70.74	611.07



LEGAL DESCRIPTION

<u>LEGAL DESCRIPTION:</u> (PER OFFICIAL RECORDS BOOK 3842, PAGE 1386)

A PARCEL OF LAND LOCATED IN SECTION 20, TOWNSHIP 8 SOUTH, RANGE 19 EAST, ALACHUA COUNTY, FLORIDA AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCE AT A FOUND IRON PIN MARKING THE SOUTHEAST CORNER OF SECTION 20, TOWNSHIP 8 SOUTH, RANGE 19 EAST, ALACHUA COUNTY, FLORIDA; THENCE WEST A DISTANCE OF 1313.40 FEET TO A POINT; THENCE NORTH A DISTANCE OF 218.99 FEET TO A FOUND 3/4" IRON PIN MARKING A POINT ON THE NORTH RIGHT-OF-WAY LINE OF U. S. HIGHWAY NO. 441 (200 FOOT RIGHT-OF-WAY); THENCE ALONG SAID NORTH RIGHT-OF-WAY LINE; NORTH 72 DEG. 51 MIN. 49 SEC. WEST A DISTANCE OF 171.11 FEET TO A FOUND 5/8 INCH IRON PIN (FLORIDA D.O.T.) MARKING THE POINT OF CURVATURE OF A CURVE CONCAVE TO THE NORTHEAST, HAVING A DELTA OF 06 DEG. 52 MIN. 05 SEC., A RADIUS OF 11424.66 FEET AND A CHORD BEARING NORTH 69 DEG. 24 MIN. 13 SEC. WEST, 1368.62 FEET; THENCE ALONG THE ARC OF SAID CURVE A DISTANCE OF 1369.44 FEET TO A FOUND 6" X 6" CONCRETE MONUMENT (FLORIDA D.O.T.); THENCE NORTH 65 DEG. 59 MIN. 42 SEC. WEST A DISTANCE OF 1385.74 FEET TO A FOUND 5/8 INCH REBAR AND CAP (#3524); THENCE DEPARTING SAID NORTH RIGHT-OF-WAY LINE, NORTH 22 DEG. 09 MIN. 10 SEC. EAST A DISTANCE OF 159.44 FEET TO A FOUND 5/8 INCH REBAR AND CAP (#3524); THENCE NORTH 66 DEG. 13 MIN. 12 SEC. WEST A DISTANCE OF 229.98 FEET TO A FOUND 5/8 INCH REBAR AND CAP (#3524); THENCE NORTH 01 DEG. 33 MIN. 25 SEC. EAST A DISTANCE OF 169.02 FEET TO A FOUND 4" X 4" CONCRETE MONUMENT (PLS #940) MARKING THE POINT OF BEGINNING; THENCE NORTH 23 DEG. 50 MIN. 23 SEC. EAST A DISTANCE OF 2014.63 FEET TO A SET 5/8 INCH REBAR AND CAP (#3524) MARKING A POINT ON THE SOUTH RIGHT-OF-WAY LINE OF SEABOARD COAST LINE RAILROAD (200 FOOT RIGHT-OF-WAY); THENCE ALONG SAID SOUTH RIGHT-OF-WAY LINE OF SEABOARD COAST LINE RAILROAD, NORTH 58 DEG. 44 MIN. 53 SEC. WEST A DISTANCE OF 624.24 FEET TO A FOUND 5/8 INCH REBAR AND CAP (#3524); THENCE DEPARTING SAID SOUTH RIGHT-OF-WAY LINE, SOUTH OO DEG. 37 MIN. 49 SEC. EAST A DISTANCE OF 70.65 FEET TO A FOUND 5/8 INCH REBAR AND CAP (#3524); THENCE NORTH 58 DEG. 44 MIN. 53 SEC. WEST A DISTANCE OF 547.93 FEET TO A FOUND 5/8 INCH REBAR AND CAP (#3524) MARKING THE POINT OF CURVATURE OF A CURVE CONCAVE TO THE SOUTHWEST, HAVING A DELTA OF 10 ĎEG. 0Ó MIN. 21 SEC., A RADIUS OF 2712.57 FEET AND A CHORD BEARING NORTH 63 DEG. 45 MIN. 03 SEC. WEST, 473.11 FEET; THENCE ALONG THE ARC OF SAID CURVE A DISTANCE OF 473.71 FEET TO A FOUND 5/8 INCH REBAR AND CAP (#3524); THENCE SOUTH 00 DEG. 08 MIN. 45 SEC. WEST A DISTANCE OF 2657.79 FEET TO A FOUND 5/8 INCH REBAR AND CAP (#3524) MARKING A POINT ON SAID NORTH RIGHT-OF-WAY LINE OF U. S. HIGHWAY NO. 441; THENCE ALONG SAID NORTH RIGHT-OF-WAY LINE, SOUTH 66 DEG 00 MIN. 09 SEC. EAST A DISTANCE OF 209.40 FEET TO A FOUND 4" X 4" CONCRETE MONUMENT; THENCE DEPARTING SAID NORTH RIGHT-OF-WAY LINE, NORTH 01 DEG. 07 MIN. 22 SEC. EAST A DISTANCE OF 340.98 FEET TO A FOUND 4" X 4" CONCRETE MONUMENT; THENCE SOUTH 65 DEG. 57 MIN. 03 SEC. EAST A DISTANCE OF 460.08 FEET TO THE POINT OF BEGINNING

TOGETHER WITH A PERPETUAL, NON-EXCLUSIVE AND UNRESTRICTED EASEMENT OVER, UNDER AND ACROSS THE FOLLOWING TWO PARCELS OF REAL PROPERTY.


EASEMENT PARCEL #1

COMMENCE AT THE HALF MILE CORNER OR THE NORTH LINE OF SECTION 19, TOWNSHIP 8 SOUTH, RANGE 19 EAST, AND RUN SOUTH 499.11 FEET TO THE SOUTHERLY RIGHT—OF—WAY LINE OF THE SEABOARD COASTLINE RAILROAD; THENCE RUN, SOUTH 81 DEG. 45' 10" EAST ALONG SAID SOUTHERLY RIGHT—OF—WAY 1INE 2797.03 FEET TO THE P.C. OF A CURVE CONCAVE TO THE 50UTHWEST AND HAVING A RADIUS AT 2764.93 FEET; THENCE RUN SOUTHEASTER1Y ALONG SAID SOUTHERLY RIGHT—OF—WAY LINE AN ARC DISTANCE OF 498.99 FEET TO A CONCRETE MONUMENT AT THE NORTHWEST CORNER OF GENERAL ELECTRIC CO. PROPERTY, SAID POINT BEING THE P.O.B.; THENCE CONTINUE SOUTHEASTERLY ALONG SAID RIGHT—OF—WAY AN ARC DISTANCE OF 31.68 FEET AND A CHORD BEARING AND DISTANCE OF SOUTH 7L DEG. 06' 52" EAST 31.68 FEET; THENCE RUN SOUTH 00 DEG. 08' 45" WEST PARALLEL WITH AND 30 FEET FROM THE WEST LINE OF SAID GENERAL ELECTRIC CO. PROPERTY, 2718.29 FEET TO THE NORTHERLY RIGHT—OF—WAY LINE AT U.S. HIGHWAY NO. 441 (STATE ROAD NO. 25); THENCE RUN NORTH 66 DEG. 00' 06" WEST ALONG SAID RIGHT—OF—WAY LINE 32.8 FEET TO THE SOUTHWEST CORNER OF SAID PROPERTY, BEING A CONCRETE MONUMENT; THENCE RUN NORTH 00 DEG. 08' 45" EAST ALONG THE WEST LINE AT SAID PROPERTY 2715.11 FEET TO THE P.O.B., BEING AND LYING IN SECTION 30, TOWNSHIP 8 SOUTH, RANGE 19 EAST, ALACHUA COUNTY, FLORIDA.

EASEMENT PARCEL ;

COMMENCE AT THE HALF MILE CORNER ON THE NORTH LINE OR SECTION 19, TOWNSHIP 8 SOUTH, RANGE 19 EAST AND RUN SOUTH 499.11 FEET TO THE SOUTHERLY RIGHT-OF-WAY LINE OF THE SEABOARD COASTLINE RAILROAD; THENCE RUN SOUTH 81 DEG. 45' 18" EAST ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE 2797.03 FEET TO THE P.C. OF A CURVE CONCAVE TO THE SOUTHWEST AND HAVING A RADIUS OF 2764.93 FEET; THENCE RUN SOUTHEASTERLY ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE AN ARC DISTANCE OF 498.99 FEET TO A CONCRETE MONUMENT AT THE NORTHWEST CORNER OF GENERAL ELECTRIC CO. PROPERTY; THENCE CONTINUE SOUTHEASTERLY ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE AN ARC DISTANCE OF 31.68 FEET AND A CHORD BEARING AND DISTANCE OF SOUTH 71 DEG. 06' 52" EAST 31.68 FEET TO THE P.O.B.; THENCE CONTINUE SOUTHEASTERLY ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE AN ARC DISTANCE OF 582.25 FEET AND A CHORD BEARING AND DISTANCE OF SOUTH 64 DEG. 45' 10" EAST 581.11 FEET TO THE P.T. OF SAID CURVE; THENCE CONTINUE ALONG SAID RLQHT-OF-WAY LINE SOUTH 58 DEG. 43' 12" EAST 510.61 FEET; THENCE RUN SOUTH 00 DEG. 37' 54" EAST 70.68 FEET; THENCE RUN NORTH 58 DEG. 43' 12" WEST PARALLEL WITH AND 60 FEET FROM THE SOUTHERLY RIGHT-OF-WAY LINE OF SAID RAILROAD, 547.97 FEET TO THE P.C. OF A CURVE CONCAVE TO THE SOUTHWEST AND HAVING A RADIUS AT 2704.93 FEET; THENCE RUN NORTHWESTERLY ALONG SAID CURVE AN ARC DISTANCE OF 484.91 FEET AND A CHORD BEARING AND DISTANCE OF NORTH 63 DEG. 51' 21" WEST 484.26 FEET; THENCE RUN SOUTH 08 DEG. 08' 45" WEST PARALLEL WITH AND 90 FEET EAST OF THE WEST LINE OF SAID G. E. PROPERTY 2659.10 FEET TO THE NORTH RIGHT-OF-WAY LINE OF U.S. HIGHWAY NO. 441 (STATE ROAD NO. 25); THENCE RUN NORTH 66 DEG. 00' 06" WEST ALONG SAID RIGHT-OF-WAY LINE 65.6 FEET; THENCE RUN NORTH 00 DEG. 08' 45" EAST 2718.2 FEET TO THE P.O.B. BEING AND LYING IN SECTION 20, TOWNSHIP 8 SOUTH, RANGE 19 EAST, ALACHUA COUNTY, FLORIDA.

DRAWING INDEX				
SHEET NUMBER SHEET TITLE				
C0.00	COVER SHEET			
C0.10	LEGEND, SYMBOLS AND NOTES			
C0.20	DEVELOPMENT PLAN			
C0.30	TREE CLEARING PLAN			
C1.00	DIMENSION PLAN			
C2.00	PAVING, GRADING AND DRAINAGE PLAN			
C2.10	PAVING, GRADING AND DRAINAGE DETAILS AND NOTES			
C2.20	BASIN 1 DETAIL			
C2.30	BASIN 2 DETAIL			
C3.00	STORMWATER POLLUTION PREVENTION PLAN			
C4.00	UTILITY PLAN			
C4.10	UTILITY DETAILS			
V001-V012	BOUNDARY AND TOPOGRAPHIC SURVEY			
A100-A202	ARCHITECTURAL PLANS			
L101-L304	LANDSCAPE			
E	PHOTOMETRIC			



engineers • surveyors • planners

2404 N.W. 43rd ST, GAINESVILLE, FLORIDA 32606-6602 TEL. (352) 373-3541 FAX. (352) 373-7249



	Engine	er Ce
roject	No:	18-023
roject	nhase.	

SAN FELASCO TECH CITY CITY OF ALACHUA,

FLORIDA

CITY SUBMITTAL


Sheet title:

Project title:

COVER SHEET

Designe	ed:	SJR	She
Drawn:		MAB	
Checke	:d:	TAR	
Date:	06,	/25/18	

C0.00



GENERAL NOTES

- 1. LOCATIONS, ELEVATIONS, AND DIMENSIONS OF EXISTING UTILITIES, STRUCTURES AND OTHER FEATURES ARE SHOWN ACCORDING TO THE BEST INFORMATION AVAILABLE AT THE TIME OF PREPARATION OF THESE PLANS. THE CONTRACTOR SHALL VERIFY THE LOCATIONS, ELEVATIONS, AND DIMENSIONS OF ALL EXISTING UTILITIES, STRUCTURES AND OTHER FEATURES, AFFECTING THIS WORK, PRIOR TO
- 2. PRIOR TO THE INITIATION OF SITE CONSTRUCTION, THE CONTRACTOR SHALL VERIFY ANY EXISTING UTILITIES INCLUDING GAS, WATER, ELECTRIC, CABLE TV, COMMUNICATIONS, SANITARY SEWERS AND STORM DRAINAGE SYSTEMS, ON AND/OR ADJACENT TO THE SITE. REMOVE OR CAP AS NECESSARY. CONTACT ENGINEER OF RECORD IMMEDIATELY WITH ANY DISCREPANCIES.
- 3. THE CONTRACTOR IS RESPONSIBLE FOR REPAIRING ANY DAMAGE TO EXISTING FACILITIES. ABOVE OR BELOW GROUND. THAT MAY OCCUR AS A RESULT OF THE WORK PERFORMED, BY THE CONTRACTOR OR SUB-CONTRACTORS, AS CALLED FOR IN THESE CONTRACT DOCUMENTS.
- 4. CONTRACTOR TO COORDINATE WITH UTILITY COMPANIES FOR THE RELOCATION OF EXISTING UTILITIES. UTILITIES NEEDING TO BE REMOVED OR RELOCATED SHALL BE COORDINATED WITH THE AFFECTED UTILITY COMPANY. ADEQUATE TIME SHALL BE PROVIDED FOR RELOCATION, AND CLOSE COORDINATION WITH THE UTILITY COMPANY IS NECESSARY TO PROVIDE A SMOOTH TRANSITION IN UTILITY SERVICE. THE CONTRACTOR SHALL COORDINATE WITH THE UTILITY COMPANY CONCERNING PORTIONS OF THE WORK WHICH MAY BE PERFORMED BY THE UTILITY COMPANY'S FORCES AND ANY FEES WHICH ARE TO BE PAID TO THE UTILITY COMPANY FOR THEIR SERVICES. THE CONTRACTOR IS RESPONSIBLE FOR PAYING ALL FEES AND
- 5. IT IS THE CONTRACTOR'S RESPONSIBILITY TO BECOME FAMILIAR WITH THE PERMIT AND INSPECTION REQUIREMENTS SPECIFIED BY THE VARIOUS GOVERNMENTAL AGENCIES AND THE ENGINEER. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS PRIOR TO CONSTRUCTION, AND SCHEDULE INSPECTIONS ACCORDING TO AGENCY INSTRUCTION/REQUIREMENTS.
- 6. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS, ON ALL PRECAST AND MANUFACTURED ITEMS, TO THE OWNER'S ENGINEER FOR REVIEW. FAILURE TO OBTAIN APPROVAL BEFORE INSTALLATION MAY RESULT IN REMOVAL AND REPLACEMENT AT THE CONTRACTOR'S EXPENSE.
- 7. SAFETY:
- A. DURING THE CONSTRUCTION AND OR MAINTENANCE OF THIS PROJECT. ALL SAFETY REGULATIONS ARE TO BE ENFORCED. THE CONTRACTOR OR HIS REPRESENTATIVE SHALL BE RESPONSIBLE FOR THE CONTROL AND SAFETY OF
- THE TRAVELING PUBLIC AND THE SAFETY OF HIS/HER PERSONNEL. B. LABOR SAFETY REGULATIONS SHALL CONFORM TO THE PROVISIONS SET FORTH C. THE MINIMUM STANDARDS AS SET FORTH IN THE CURRENT EDITION OF "THE
- STATE OF FLORIDA, MANUAL ON TRAFFIC CONTROL AND SAFE PRACTICES FOR STREET AND HIGHWAY CONSTRUCTION, MAINTENANCE AND UTILITY OPERATIONS" SHALL BE FOLLOWED IN THE DESIGN, APPLICATION, INSTALLATION, MAINTENANCE AND REMOVAL OF ALL TRAFFIC CONTROL DEVICES, WARNING DEVICES AND BARRIERS NECESSARY TO PROTECT THE PUBLIC AND CONSTRUCTION PERSONNEL FROM HAZARDS WITHIN THE PROJECT LIMITS.
- D. ALL TRAFFIC CONTROL MARKINGS AND DEVICES SHALL CONFORM TO THE PROVISIONS SET FORTH IN THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES PREPARED BY THE U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION.
- E. ALL SUBSURFACE CONSTRUCTION SHALL COMPLY WITH THE "TRENCH SAFETY ACT". THE CONTRACTOR SHALL INSURE THAT THE METHOD OF TRENCH PROTECTION AND CONSTRUCTION IS IN COMPLIANCE WITH THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REGULATIONS.
- IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO COMPLY AND ENFORCE ALL APPLICABLE SAFETY REGULATIONS. THE ABOVE INFORMATION HAS BEEN PROVIDED FOR THE CONTRACTOR'S INFORMATION ONLY AND DOES NOT IMPLY THAT THE OWNER OR ENGINEER WILL INSPECT AND/OR ENFORCE SAFETY REGULATIONS.
- 8. ALL UNDERGROUND UTILITIES MUST BE IN-PLACE, TESTED AND INSPECTED PRIOR TO BASE AND SURFACE CONSTRUCTION.
- 9. CONTRACTOR IS REQUIRED TO SECURE A FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION (FDEP) "NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM" (NPDES) PERMIT BEFORE BEGINNING CONSTRUCTION.
- 10. A COMPLETE SET OF PERMITTED DRAWINGS AND SPECIFICATIONS MUST BE MAINTAINED ON SITE AT ALL TIMES THAT THE CONTRACTOR IS PERFORMING WORK. THESE DRAWINGS SHALL BE MADE AVAILABLE UPON REQUEST.
- 11. ALL EROSION AND SEDIMENT CONTROL DEVICES SHALL BE CONSTRUCTED SIMULTANEOUSLY WITH THE DISTURBANCE OF THE LAND AND SHALL REMAIN FUNCTIONAL UNTIL THE CONTRIBUTING DISTURBED AREAS ARE STABILIZED. SILT BARRIERS WILL BE INSTALLED AS NECESSARY TO PREVENT EXCESSIVE SEDIMENTATION OF DOWNSTREAM AREAS.
- 12. CONTRACTOR SHALL PROVIDE CITY AS-BUILT PLANS (IF REQUIRED BY THE CITY AND/OR ANY OTHER AGENCY), SIGNED AND SEALED BY A FLORIDA REGISTERED ENGÍNEER OR SURVEYOR AND A CERTIFIED PAPER COPY WITH ELECTRONIC COPY IN AUTOCAD FORMAT PRIOR TO FINAL ACCEPTANCE.
- 13. THE CONTRACTOR SHALL CONSTRUCT GRAVITY SEWER LATERALS, MANHOLES GRAVITY SEWER LINES AND DOMESTIC WATER AND FIRE PROTECTION SYSTEM AS SHOWN ON THESE PLANS. THE CONTRACTOR SHALL FURNISH ALL NECESSARY MATERIALS, EQUIPMENT, MACHINERY, TOOLS, MEANS OF TRANSPORTATION AND LABOR NECESSARY TO COMPLETE THE WORK IN FULL AND COMPLETE ACCORDANCE WITH THE SHOWN, DESCRIBED AND REASONABLY INTENDED REQUIREMENTS OF THE CONTRACT DOCUMENTS AND JURISDICTIONAL AGENCY REQUIREMENTS. IN THE EVENT THAT THE CONTRACT DOCUMENTS AND THE JURISDICTIONAL AGENCY REQUIREMENTS ARE NOT IN AGREEMENT, THE MOST STRINGENT SHALL GOVERN.
- 14. CONTRACTOR TO FOLLOW ALL CRITERIA SET FORTH BY THE CITY OF ALACHUA REQUIREMENTS FOR POTABLE WATER, RECLAIMED WATER, AND WASTEWATER.

DEMOLITION NOTES

- ALL MATERIAL REMOVED FROM THIS SITE BY THE CONTRACTOR SHALL BE DISPOSED OF BY THE CONTRACTOR IN A LEGAL MANNER.
- 2. REFER TO THE TOPOGRAPHIC SURVEY FOR ADDITIONAL DETAILS OF EXISTING STRUCTURES, ETC., LOCATED WITHIN THE PROJECT SITE. UNLESS OTHERWISE NOTED, ALL EXISTING BUILDINGS, STRUCTURES, SLABS, CONCRETE, ASPHALT, DEBRIS PILES, SIGNS, AND ALL APPURTENANCES ARE TO BE REMOVED FROM THE SITE BY THE CONTRACTOR AND PROPERLY DISPOSED OF IN A LEGAL MANNER AS PART OF THIS CONTRACT. SOME ITEMS TO BE REMOVED MAY NOT BE DEPICTED ON THE TOPOGRAPHIC SURVEY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VISIT THE SITE AND DETERMINE THE FULL EXTENT OF ITEMS TO BE REMOVED. IF ANY ITEMS ARE IN QUESTION, THE CONTRACTOR SHALL CONTACT THE OWNER PRIOR TO REMOVAL OF
- 3. THE CONTRACTOR SHALL REFER TO THE DEMOLITION PLAN FOR DEMOLITION / PRESERVATION OF EXISTING TREES. ALL TREES NOT SPECIFICALLY SHOWN TO BE PRESERVED OR RELOCATED SHALL BE REMOVED AS A PART OF THIS CONTRACT. TREE PROTECTION FENCING SHALL BE INSTALLED PRIOR TO ANY DEMOLITION.
- 4. CONTRACTOR SHALL SUBMIT DEMOLITION SCHEDULE TO OWNER PRIOR TO PROCEEDING WITH DEMOLITION ACTIVITIES.
- 5. CONDUCT SITE DEMOLITION OPERATIONS TO ENSURE MINIMUM INTERFERENCE WITH ROADS. STREETS. WALKS. AND OTHER ADJACENT OCCUPIED OR USED FACILITIES. DO NOT CLOSE OR OBSTRUCT STREETS, WALKS, OR OTHER OCCUPIED OR USED FACILITIES WITHOUT PERMISSION FROM AUTHORITIES HAVING JURISDICTION. CLOSURE OF THESE FACILITIES MAY REQUIRE A MAINTENANCE OF TRAFFIC PLAN PREPARED BY A REGISTERED PROFESSIONAL AT THE CONTRACTORS EXPENSE.
- 6. PROVIDE PROTECTION AS NECESSARY TO PREVENT DAMAGE TO EXISTING IMPROVEMENTS SHOWN IN THE PLANS TO REMAIN.
- 7. LOCATE EXISTING ABOVE GROUND AND UNDERGROUND UTILITIES IN AREAS OF WORK. IF UTILITIES ARE TO REMAIN IN PLACE, PROVIDE ADEQUATE MEANS OF SUPPORT AND PROTECTION DURING DEMOLITION AND CONSTRUCTION OPERATIONS.
- CONTRACTOR SHALL COORDINATE WITH APPLICABLE UTILITY COMPANIES FOR THE TERMINATION, CAPPING-OFF AND REMOVAL OF ALL EXISTING UNDERGROUND AND ABOVE GROUND UTILITY SERVICES UNLESS DIRECTED TO OTHERWISE.

CONSTRUCTION NOTES

- 1. SIGNS AND BARRICADES SHALL BE IN ACCORDANCE WITH THE U.S. DEPARTMENT OF TRANSPORTATION'S "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES", AND THE FLORIDA DEPARTMENT OF TRANSPORTATION'S 'ROADWAY AND TRAFFIC DESIGN STANDARDS"INDEXES 600 THROUGH 685 (LATEST EDITIONS).
- 2. SAFE PEDESTRIAN TRAFFIC IS TO BE MAINTAINED AT ALL TIMES.
- ANY SIDEWALK WHICH BECOMES UNDERMINED MUST BE REMOVED AND REPLACED. SIDEWALKS ARE TO BE RECONSTRUCTED WITHIN THREE (3) DAYS AFTER REMOVAL. WHEN EXISTING SIDEWALK IS REMOVED, IT IS TO BE REMOVED TO THE NEAREST
- 4. DISTURBED AREA WITHIN THE R-O-W WILL BE COMPACTED TO 98% OF MAXIMUM DENSITY AND SODDED.
- 5. STOCKPILING OF MATERIAL IS NOT ALLOWED ON ROADWAYS OR SIDEWALKS. ALL DIRT AND DEBRIS WILL BE REMOVED FROM JOB SITE DAILY. ROADS AND SIDEWALKS ARE TO BE SWEPT DAILY AS PART OF DAILY CLEANUP.
- 6. ANY PORTION OF ROADWAYS OR SIDEWALKS THAT SUSTAIN EXCESSIVE CONSTRUCTION RELATED DAMAGE, IN THE OPINION OF APPLICABLE AGENCIES, SHALL BE REPAIRED AT CONTRACTOR EXPENSE IN A MANNER SPECIFIED BY THAT
- CONSTRUCTION MUST BE PER THE APPROVED SITE PLAN OF THE DRC (OR EQUIVALENT). DEVIATIONS IN ROADWAY, UTILITY OR DRAINAGE CONSTRUCTION WILL REQUIRE PRIOR WRITTEN APPROVAL OF THE CITY ENGINEER OR THE DIRECTOR OF PUBLIC SERVICES (OR EQUIVALENT). NOTE: SIGNIFICANT CHANGES FROM THE DRC APPROVED PLAN MAY REQUIRE THE OWNER/DEVELOPER TO SUBMIT A REVISED SITE PLAN FOR REVIEW THROUGH THE DRC AND MAY CAUSE PROJECT DELAYS.
- 8. OFF-SITE OR ROADWAY R-O-W CONSTRUCTION SHALL BE IN ACCORDANCE WITH ALL CONDITIONS OF THE APPROVED R-O-W PERMIT(S). A COPY OF THE APPROVED R-O-W PERMIT MUST BE KEPT ON-SITE AND READILY AVAILABLE DURING ALL CONSTRUCTION ACTIVITIES WITHIN THE R-O-W.
- 9. DURING THE CONSTRUCTION AND/OR MAINTENANCE OF THIS PROJECT, ALL SAFETY REGULATIONS ARE TO BE ENFORCED. THE CONTRACTOR OR HIS REPRESENTATIVE SHALL BE RESPONSIBLE FOR THE CONTROL AND SAFETY OF THE TRAVELING PUBLIC AND THE SAFETY OF HIS/HER PERSONNEL.
- 10. ALL CONSTRUCTION. MATERIALS AND WORKMANSHIP ARE TO BE IN ACCORDANCE WITH FLORIDA DEPARTMENT OF TRANSPORTATION SPECIFICATIONS AND STANDARDS.
- 11. CONTRACTOR IS RESPONSIBLE FOR CHECKING ACTUAL SITE CONDITIONS BEFORE STARTING CONSTRUCTION.
- 12. ANY DISCREPANCIES ON THE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER BEFORE COMMENCING WORK.
- 13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL REQUIRED CONSTRUCTION PERMITS AND BONDS IF REQUIRED PRIOR TO CONSTRUCTION.
- 14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTING TO THE ENGINEER A CERTIFIED RECORD SURVEY SIGNED AND SEALED BY A PROFESSIONAL LAND SURVEYOR REGISTERED IN THE STATE OF FLORIDA DEPICTING THE ACTUAL FIELD LOCATION OF ALL CONSTRUCTED IMPROVEMENTS THAT ARE REQUIRED BY THE JURISDICTIONAL AGENCIES FOR THE CERTIFICATION PROCESS. ALL SURVEY COSTS WILL BE THE CONTRACTORS RESPONSIBILITY. BOTH PAPER AND AUTOCAD FILES
- 15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DOCUMENTING AND MAINTAINING AS-BUILT INFORMATION WHICH SHALL BE RECORDED AS CONSTRUCTION PROGRESSES OR AT THE COMPLETION OF APPROPRIATE CONSTRUCTION INTERVALS AND SHALL BE RESPONSIBLE FOR PROVIDING AS-BUILT DRAWINGS TO THE OWNER FOR THE PURPOSE OF CERTIFICATION TO JURISDICTIONAL AGENCIES AS REQUIRED. BOTH PAPER AND AUTOCAD SHALL BE PROVIDED.

EROSION CONTROL NOTES

- 1. THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS COMPRISED OF THE FROSION CONTROL PLAN THE STANDARD DETAILS. THE PLAN NARRATIVE. ATTACHMENTS REFERENCED BY THE SWPPP, PLUS THE PERMIT AND ALL SUBSEQUENT REPORTS AND RELATED DOCUMENTS.
- 2. ALL CONTRACTORS AND SUBCONTRACTORS INVOLVED WITH STORM WATER POLLUTION PREVENTION SHALL OBTAIN A COPY OF THE STORM WATER POLLUTION PREVENTION PLAN AND THE STATE OF FLORIDA NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM GENERAL PERMIT (NPDES PERMIT) AND BECOME FAMILIAR WITH
- THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES AS REQUIRED BY THE SWPPP. ADDITIONAL BEST MANAGEMENT PRACTICES SHALL BE IMPLEMENTED AS DICTATED BY CONDITIONS AT NO ADDITIONAL COST TO THE OWNER THROUGHOUT ALL PHASES OF CONSTRUCTION.
- 4. PERMITS FOR ANY CONSTRUCTION ACTIVITY IMPACTING STATE WATERS OR REGULATED WETLANDS MUST BE MAINTAINED ON SITE AT ALL TIMES.
- 5. ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DETAINED AND PROPERLY TREATED OR DISPOSED.
- 6. SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOTATION BOOMS SHALL BE MAINTAINED ON SITE OR READILY AVAILABLE TO CONTAIN AND CLEAN-UP FUEL OR CHEMICAL SPILLS AND LEAKS.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DUST CONTROL ON SITE. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS PROHIBITED.
- RUBBISH, TRASH, GARBAGE, LITTER, OR OTHER SUCH MATERIALS SHALL BE DEPOSITED INTO SEALED CONTAINERS. MATERIALS SHALL BE PREVENTED FROM
- LEAVING THE PREMISES THROUGH THE ACTION OF WIND OR STORM WATER RUNOFF. 9. ALL STORM WATER POLLUTION PREVENTION MEASURES PRESENTED ON THE PLAN
- SHALL BE INITIATED AS SOON AS PRACTICABLE. 10. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS PERMANENTLY STOPPED SHALL BE PERMANENTLY SEEDED. THESE AREAS SHALL BE
- SEEDED NO LATER THAN 7 DAYS AFTER THE LAST CONSTRUCTION ACTIVITY OCCURRED IN THESE AREAS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING SEDIMENT IN THE DETENTION POND AND ANY SEDIMENT THAT MAY HAVE COLLECTED IN THE STORM DRAINS IN CONJUNCTION WITH THE STABILIZATION OF THE SITE.
- 12. ON-SITE & OFF SITE SOIL STOCKPILE AND BORROW AREAS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION THROUGH IMPLEMENTATION OF BEST MANAGEMENT PRACTICES. STOCKPILE AND BORROW AREA LOCATIONS SHALL BE NOTED ON THE EROSION CONTROL PLAN BY THE CONTRACTOR AND PERMITTED IN ACCORDANCE WITH GENERAL PERMIT REQUIREMENTS.
- 13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING THE EROSION CONTROL MEASURES (SILT FENCES, STABILIZATION, SEDIMENT BASINS, ETC.) AS NEEDED FOR EACH STAGE OF SITE WORK / GRADING.
- 14. NO GRADING, CUTTING, OR FILLING SHALL COMMENCE UNTIL SUCH TIME AS APPROPRIATE EROSION AND SEDIMENTATION CONTROL DEVICES HAVE BEEN INSTALLED BETWEEN ALL DISTURBED AREAS AND WATER BODIES. WATERCOURSES OR WETLANDS AND ANY CONVEYANCES SUCH AS DRAINAGE DITCHES, STORM DRAINS, AND INLETS.
- 15. ALL EROSION AND SEDIMENT CONTROL DEVICES SHALL BE INSTALLED PRECEEDING ANY DISTURBANCE OF THE LAND AND SHALL REMAIN FUNCTIONAL UNTIL THE CONTRIBUTING DISTURBED AREAS ARE STABILIZED. THE CONTRACTOR SHALL INSTALL ALL EROSION AND PREVENTION STRUCTURES SHOWN ON THE PLANS AT A MINIMUM AND IN FULL CONFORMANCE WITH ALL APPLICABLE WATER MANAGEMENT DISTRICT PERMITS AND REGULATIONS.
- 16. ALL CONTROL STRUCTURE AND OUTFALL CULVERT INSTALLATIONS SHALL BE PROTECTED WITH SEDIMENT BARRIERS AT A MINIMUM.
- 17. ALL DISTURBED AREAS (ABOVE NORMAL WATER LEVELS) UNLESS OTHERWISE NOTED HEREIN, SHALL BE SEEDED AND MULCHED WITHIN 7 DAYS OF FINAL GRADING. UNLESS OTHERWISE NOTED, ALL SLOPES STEEPER THAN 4:1 SHALL BE SODDED.

PAVING. GRADING. AND DRAINAGE NOTES

- 1. TRAFFIC CONTROL ON ALL FDOT, LOCAL AND COUNTY RIGHTS-OF-WAY SHALL MEET THE REQUIREMENTS OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (U.S. DOT/FHA) AND THE REQUIREMENTS OF THE STATE AND ANY LOCAL AGENCY HAVING JURISDICTION. IN THE EVENT THAT THE CONTRACT DOCUMENTS AND THE JURISDICTIONAL AGENCY REQUIREMENTS ARE NOT IN AGREEMENT, THE MOST STRINGENT SHALL GOVERN.
- 2. ALL OPEN AREAS WITHIN THE PROJECT SITE SHALL BE SODDED UNLESS INDICATED OTHERWISE ON THE
- 3. THE CONTRACTOR SHALL INSTALL FILTER FABRIC OVER ALL DRAINAGE STRUCTURES FOR THE DURATION OF CONSTRUCTION AND UNTIL ACCEPTANCE OF THE PROJECT BY THE OWNER. ALL DRAINAGE STRUCTURES SHALL BE CLEANED OF DEBRIS AS REQUIRED DURING AND AT THE END OF CONSTRUCTION TO PROVIDE POSITIVE
- 4. IF DEWATERING IS REQUIRED, THE CONTRACTOR SHALL OBTAIN ANY APPLICABLE REQUIRED PERMITS. THE CONTRACTOR IS TO COORDINATE WITH THE OWNER AND THE DESIGN ENGINEER PRIOR TO ANY EXCAVATION.
- 5. THE CONTRACTOR MUST REVIEW AND MAINTAIN A COPY OF THE ENVIRONMENTAL RESOURCE PERMIT COMPLETE WITH ALL CONDITIONS, ATTACHMENTS, EXHIBITS, AND PERMIT MODIFICATIONS IN GOOD CONDITION AT THE CONSTRUCTION SITE. THE COMPLETE PERMIT MUST BE AVAILABLE FOR REVIEW UPON REQUEST BY WATER MANAGEMENT DISTRICT REPRESENTATIVES.
- 6. THE CONTRACTOR SHALL ENSURE THAT ISLAND PLANTING AREAS AND OTHER PLANTING AREAS ARE NOT COMPACTED AND DO NOT CONTAIN ROAD BASE MATERIALS. THE CONTRACTOR SHALL ALSO EXCAVATE AND REMOVE ALL UNDESIRABLE MATERIAL FROM ALL AREAS ON THE SITE TO BE PLANTED AND PROPERLY DISPOSED OF IN A LEGAL MANNER.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING EXCAVATIONS AGAINST COLLAPSE AND WILL PROVIDE BRACING, SHEETING OR SHORING AS NECESSARY. DE-WATERING METHODS SHALL BE USED AS REQUIRED TO KEEP TRENCHES DRY WHILE PIPE AND APPURTENANCES ARE BEING PLACED.
- 8. THE CONTRACTOR WILL STABILIZE BY SEED AND MULCH, SOD, OR OTHER APPROVED MATERIALS ANY DISTURBED AREAS WITHIN ONE WEEK FOLLOWING CONSTRUCTION OF THE UTILITY SYSTEMS AND PAVEMENT AREAS. CONTRACTOR SHALL MAINTAIN SUCH AREAS UNTIL FINAL ACCEPTANCE BY OWNER. CONTRACTOR TO COORDINATE WITH OWNER REGARDING TYPE OF MATERIAL, LANDSCAPING AND IRRIGATION IMPROVEMENTS TO
- 9. SITE GRADING, PAVING AND DRAINAGE MATERIALS AND CONSTRUCTION SHALL CONFORM TO FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
- IMMEDIATELY AT ONSET OF CONSTRUCTION, CONTRACTOR SHALL FIELD VERIFY HORIZONTAL AND VERTICAL LOCATIONS OF ALL EXISTING UTILITIES CRITICAL TO COMPLETING THE PROJECT (INCLUDING WATER, SEWER, POWER, TELEPHONE, GAS, AND CABLE TV) AND SHALL EVALUATE POTENTIAL CONFLICTS. ALL SUCH CONFLICTS SHALL BE REPORTED TO ENGINEER/OWNER IMMEDIATELY UPON DISCOVERY.
- 11. PRIOR TO CONSTRUCTION, CONTRACTOR SHALL FIELD STAKE AND ROPE OFF CONSERVATION AREA LINES. OWNER RESERVES THE RIGHTS TO CHECK THE STAKING AND ROPING AND REQUIRE IT TO BE RELOCATED IF NECESSARY. IT SHALL REMAIN IN PLACE UNTIL ADJACENT CONSTRUCTION IS COMPLETE.
- 12. CONTRACTOR SHALL BE EXTREMELY CAUTIOUS WHEN WORKING NEAR TREES WHICH ARE TO BE SAVED, WHETHER SHOWN IN THE PLANS OR DESIGNATED IN THE FIELD.
- 13. ALL SIGNAGE, PAVEMENT MARKING AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH FDOT "ROADWAY AND TRAFFIC DESIGN STANDARDS" AND FHWA "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES".
- 14. REGULATORY SIGNS (STOP, ETC.) SHALL BE PAID FOR BY THE CONTRACTOR AND IN PLACE PRIOR TO FINAL INSPECTION OF PAVING AND DRAINAGE IMPROVEMENTS.
- 15. BLUE REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED OPPOSITE FIRE HYDRANTS IN THE CENTER OF THE NEAREST TRAVELED LANE TO MARK THEIR LOCATIONS.
- 16. CONTRACTOR IS RESPONSIBLE FOR GRADING ALL PAVEMENTS TO DRAIN POSITIVELY. INTERSECTIONS SHALL BE TRANSITIONED TO PROVIDE SMOOTH DRIVING SURFACE WHILE MAINTAINING POSITIVE DRAINAGE. SHOULD AREAS OF POOR DRAINAGE BE OBSERVED, CONTRACTOR SHALL NOTIFY THE ENGINEER PRIOR TO PLACEMENT OF CURBS OR PAVEMENT COURSES, SO THAT RECOMMENDATIONS FOR CORRECTION MAY BE MADE.
- 17. PROPOSED AND EXISTING SIDEWALKS SHALL BE RAMPED FLUSH WITH PAVEMENT. RAMPS SHALL NOT EXCEED SLOPES OF 14 HORIZONTAL TO 1 VERTICAL.
- 18. FINISHED FLOOR ELEVATIONS ARE MINIMUM ELEVATIONS REQUIRED TO SATISFY DRAINAGE AND/OR 100-FLOODPLAIN REQUIREMENTS. PAD ELEVATIONS, IMMEDIATELY OUTSIDE OF BUILDING WALLS, SHALL BE NO MORE THAN 8 INCHES BELOW THE FINISHED FLOOR ELEVATIONS SHOWN.
- 19. CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING AND DISPOSING ALL WASTE MATERIALS CONSISTENT WITH ALL RULES AND REGULATIONS APPLICABLE TO THE SPECIFIC MATERIAL FOUND. ALL DELETERIOUS SUBSURFACE MATERIAL (I.E. MUCK, PEAT, BURIED DEBRIS, ETC.) IS TO BE EXCAVATED AND REPLACED WITH SUITABLE/COMPACTED SOILS, AS DIRECTED BY THE OWNER, THE OWNERS ENGINEERS, OR OWNERS SOILS TESTING COMPANY. DELETERIOUS MATERIAL IS TO BE STOCKPILED OR REMOVED FROM THE SITE AS DIRECTED BY THE OWNER. EXCAVATED AREAS ARE TO BE BACKFILLED WITH APPROVED MATERIALS AND COMPACTED AS SHOWN ON THESE PLANS. CONTRACTOR IS RESPONSIBLE FOR ACQUIRING ANY PERMITS THAT ARE NECESSARY FOR REMOVING DELETERIOUS MATERIAL FROM THE SITE.
- 20. ALL NECESSARY FILL AND EMBANKMENT THAT IS PLACED DURING CONSTRUCTION SHALL CONSIST OF MATERIAL SPECIFIED BY THE OWNER'S SOILS TESTING COMPANY OR ENGINEER AND BE PLACED AND COMPACTED
- 21. PROPOSED SPOT ELEVATIONS REPRESENT FINISHED PAVEMENT, SIDEWALK, OR GROUND SURFACE GRADES,
- 22. CURBING SHALL BE PLACED AT THE EDGES OF ALL PAVEMENT, UNLESS OTHERWISE NOTED. REFER TO THE LATEST EDITION OF F.D.O.T. "ROADWAY AND TRAFFIC DESIGN STANDARDS" FOR DETAILS AND SPECIFICATIONS OF ALL FDOT TYPE CURB AND GUTTERS CALLED FOR IN THESE PLANS.
- 23. THE CONTRACTOR SHALL RESTORE OFF-SITE CONSTRUCTION AREAS TO EQUAL AND/OR BETTER CONDITION THAN EXISTING PRIOR TO START OF CONSTRUCTION.
- 24. UNLESS OTHERWISE NOTED, GRADE TO MEET EXISTING ELEVATION AT PROPERTY LINES.

ACCORDING TO THESE PLANS.

UNLESS OTHERWISE NOTED.

- 25. SURVEY MONUMENTS OR BENCHMARKS, WHICH HAVE TO BE DISTURBED BY THIS WORK, SHALL BE REPLACED UPON COMPLETION OF WORK BY A REGISTERED LAND SURVEYOR. ALL SURVEY COSTS WILL BE CONTRACTORS RESPONSIBILITY.
- 26. FINAL GRADES SHOWN INCLUDE SOD HEIGHT. ALL AREAS SHALL BE GRADED TO DRAIN AWAY FROM THE
- 27. IF WORK IS SUSPENDED OR DELAYED FOR 14 DAYS, THE CONTRACTOR SHALL TEMPORARILY STABILIZE THE DISTURBED AREAS AT NO ADDITIONAL COST TO THE OWNER.
- 28. STORM DRAINS SHALL BE REINFORCED CONCRETE PIPE, PER ASTM C-76 CLASS III, UNLESS OTHERWISE SPECIFIED. LIFTING HOLES ARE PROHIBITED.
- 29. ALL STORM STRUCTURES SHALL CONFORM WITH FDOT STANDARD INDEX DRAWINGS AND SPECIFICATIONS EXCEPT THAT DITCH BOTTOM INLETS IN PAVED AREAS SHALL HAVE TRAVERSABLE, TRAFFIC BEARING, GRATES SUPPORTED BY STEEL ANGLE SEATS OR SUPPORTED ON FOUR SIDES. GRATES SHALL BE CAST IRON UNLESS OTHERWISE SPECIFIED OR APPROVED.
- 30. ALL CONCRETE CURBS, SIDEWALKS, INLET TOPS, ETC. SHALL BE 3000 PSI MINIMUM, UNLESS OTHERWISE SPECIFIED.
- 31. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING APPLICABLE TESTING WITH THE SOILS ENGINEER. TESTS WILL BE REQUIRED PURSUANT WITH THE SOILS REPORT. UPON COMPLETION OF WORK THE SOILS ENGINEER WILL SUBMIT CERTIFICATIONS TO THE OWNER AND OWNER'S ENGINEER STATING THAT ALL REQUIREMENTS HAVE
- 32. A QUALIFIED TESTING LABORATORY SHALL PERFORM ALL TESTING NECESSARY TO ASSURE COMPLIANCE OF THE IN-PLACE MATERIALS AS REQUIRED BY THESE PLANS, THE VARIOUS AGENCIES AND PERMIT CONDITIONS. SHOULD ANY RETESTING BE REQUIRED DUE TO THE FAILURE OF ANY TESTS TO MEET THE REQUIREMENTS, THE CONTRACTOR WILL BEAR ALL COSTS OF SAID RETESTING
- 33. THE STORM DRAINAGE PIPING SYSTEM SHALL BE SUBJECT TO A VISUAL INSPECTION BY THE OWNER'S ENGINEER PRIOR TO THE PLACEMENT OF BACKFILL. CONTRACTOR TO NOTIFY THE ENGINEER 48 HOURS IN ADVANCE TO SCHEDULE INSPECTION.
- 34. THE CONTRACTOR SHALL MAINTAIN AND PROTECT FROM MUD. DIRT, DEBRIS, ETC. THE STORM DRAINAGE SYSTEM UNTIL FINAL ACCEPTANCE OF THE PROJECT. THE STORM SYSTEM WILL BE RE-INSPECTED BY THE OWNER'S ENGINEER PRIOR TO APPROVAL FOR CERTIFICATE OF OCCUPANCY PURPOSES. THE CONTRACTOR MAY BE REQUIRED TO RE-CLEAN PIPES AND INLETS FOR THESE PURPOSES.

Know what's **below**

Call before you dig.





2404 N.W. 43rd ST, GAINESVILLE, FLORIDA 32606-6602

TEL. (352) 373-3541 FAX. (352) 373-7249

www.edafl.com mail@edafl.com

Date Comment



18-023 Project phase:

CITY SUBMITTAL


SAN FELASCO TECH CITY CITY OF ALACHUA,


FLORIDA

Project title:


LEGEND. SYMBOLS AND NOTES


Designed: SJR Sheet No. MAB Orawn: TAR Checked: Date: 06/25/18




















1. MAINTENANCE RESPONSIBILITY:

THE LASER INVESTMENT GROUP, LLC WILL BE THE ENTITY RESPONSIBLE FOR THE MAINTENANCE OF THE PROPOSED STORMWATER MANAGEMENT SYSTEM.

MAINTENANCE NOTES

2. MAINTENANCE PLAN:

MITERED END SECTION SCHEDULE


- A. BASINS SHALL BE MOWED REGULARLY TO AVOID EXCESSIVE VEGETATIVE GROWTH.
 MOWING SCHEDULE SHOULD BE MONTHLY DURING WINTER MONTHS AND MORE FREQUENTLY (BIWEEKLY) DURING SUMMER MONTHS.
- B. BASIN SHALL BE CLEANED OUT ANNUALLY OF ANY ACCUMULATED SEDIMENTATION BUILDUP. IF THE BASINS ARE SHOWING EXCESSIVE SEDIMENTATION ACCUMULATION AT THE BASIN BOTTOM, THE BASIN BOTTOM SHALL BE SCRAPED CLEAN MORE OFTEN AS THE CONDITION DICTATES.
- C. BASIN SIDE SLOPES SHALL BE MAINTAINED WITH A GOOD STAND OF GRASS. SEASONAL GRASSES SHALL BE PLANTED TO AVOID EROSION (WINTER RYE, SUMMER MILLET).
- D. BASIN THAT DO NOT DRAWDOWN PROPERLY AND MAINTAIN STANDING WATER FOR AN EXTENDED PERIOD OF TIME MAY REQUIRE REMEDIAL ACTION. THE ENGINEER SHALL BE NOTIFIED TO HELP COORDINATE REMEDIAL ACTION IN THE EVENT THIS OCCURS.
- E. THE REQUIRED LANDSCAPING SHALL BE MAINTAINED IN A SOUND CONDITION AT ALL TIMES. ANY DEAD LANDSCAPING MATERIALS SHALL BE REPLACED IMMEDIATELY TO ASSURE PUBLIC SAFETY.

ENGINEER'S CERTIFICATION


1. ENGINEER'S CERTIFICATION:

I HEREBY CERTIFY THAT THE DESIGN OF THE STORMWATER MANAGEMENT SYSTEM FOR THE PROJECT KNOWN AS "SAN FELASCO TECH CITY" MEETS ALL THE REQUIREMENTS AND HAS BEEN
DESIGNED SUBSTANTIALLY IN ACCORDANCE WITH THE CITY OF ALACHUA STORMWATER MANAGEMENT ORDINANCE.

SERGIO REYES, P.E.




<u>PLAN VIEW</u>



PROFILE VIEW

BASIN 1 OUTFALL S-22 DETAIL



NOTES:


- 1. IF LIMESTONE OR LIMEROCK OUTCROP IS ENCOUNTERED DURING CONSTRUCTION OF THE BASIN, THE AREA WILL BE OVER-EXCAVATED A MINIMUM OF THREE FEET AND BACKFILLED WITH SUITABLE SOILS TO MEET THE SENSITIVE KARST AREA REQUIREMENTS.
- 2. IN THE EVENT A SINKHOLE, CAVITIES OR CHIMNEYS DEVELOPS WITHIN THE STORMWATER BASIN, THE FOLLOWING TREATMENT SHALL BE PERFORMED: THE OWNER SHALL NOTIFY SUWANNEE RIVER WATER MANAGEMENT DISTRICT PRIOR TO REMEDIAL ACTION UNLESS POSTPONING THE REPAIR ACTIVITY REPRESENTS AN ENDANGERMENT TO PUBLIC SAFETY. THE SINKHOLE SHALL BE BACKFILLED WITH A SANDY CLAY MIXTURE. THE SANDY CLAY SHALL BE PLACED IN SIX INCH LIFTS WITHIN THE FINAL THREE FEET OF FILL AND ROLLED WITH A HEAVILY LOADED RUBBER TIRE EQUIPMENT. SHOULD SINKHOLE ACTIVITY CONTINUE REPEATEDLY WITHIN A CONFINED AREA, THE OWNER SHALL CONSULT A GEOTECHNICAL ENGINEER TO DETERMINE WHETHER ANY ALTERNATIVE REMEDIAL MEASURES ARE REQUIRED.

LIMEROCK OUTCROP REMOVAL DETAIL


N.T.S.



engineers • surveyors • planners 2404 N.W. 43rd ST, GAINESVILLE, FLORIDA 32606-6602 TEL. (352) 373-3541 FAX. (352) 373-7249



GRAPHIC SCALE			
No.	Date	Comment	



18-023

Project phase: CITY SUBMITTAL Project title:

SAN FELASCO TECH CITY CITY OF ALACHUA, **FLORIDA**


Sheet title:

BASIN 1 DETAIL

Designed:	SJR	Sheet No.:
Drawn:	МАВ	

Checked: TAR

Date: 06/25/18



THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) MAY BE MODIFIED AND UPDATED DURING CONSTRUCTION AS A RESULT OF WEATHER. UNPREDICTABLE EVENTS AND SITE INSPECTIONS.

THIS DOCUMENT WAS PREPARED IN ORDER TO BE IN COMPLIANCE WITH CHAPTER 62-621.300 (4) OF THE FLORIDA ADMINISTRATIVE CODE, WHICH PERTAINS TO THE GENERIC PERMIT FOR STORMWATER DISCHARGE FROM LARGE AND SMALL CONSTRUCTION ACTIVITIES. THE ADMINISTRATIVE CODE GRANTS THE FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION (FDEP) THE AUTHORITY TO REGULATE POINT SOURCE DISCHARGES OF STORM-WATER FROM CONSTRUCTION SITES. THIS DOCUMENT ESTABLISHES A STORMWATER POLLUTION PREVENTION PLAN FOR THE SITE AND IS ORGANIZED TO CORRESPOND TO PART V OF DEP DOCUMENT No. 62-621.300 (4) (A) FDEP FORM 62-261.300 (4) (B) IS TO BE SUBMITTED IN CONJUNCTION WITH THIS DOCUMENT.

I. PROJECT INFORMATION:

PROJECT: SAN FELASCO TECH CITY COUNTY: ALACHUA FLORIDA SECTION/TOWNSHIP/RANGE: S 20, T 08 SOUTH, R19 EAST COUNTY PARCEL NO.: 05962-002-000 LATITUDE AND LONGITUDE: 29°26'42" N, 86°26'22" W STREET ADDRESS: 12000 BLOCK OF NW US HWY 441 PROJECT AREA: 2,414,997 S.F. APPROXIMATE AREA TO BE DISTURBED BY CONSTRUCTION:

II. SITE DESCRIPTION:

- THE PROPOSED DEVELOPMENT WILL CONSIST OF THE CONSTRUCTION OF TWO 30,100 SF BUILDINGS WITH ASSOCIATED PAVING, DRAINAGE AND UTILITY
- 2. THE SOIL CONDITIONS WERE INVESTIGATED AND SUMMARIZED IN THE SOILS REPORT PREPARED BY UNIVERSAL ENGINEERING SCIENCES. THE PROPOSED DRAINAGE PLAN WILL CONSIST OF 3 DRAINAGE AREAS. AREA (1): 3.46 ACRES OF RUNOFF WILL BE ATTENUATED BY BASIN No. (1) WHICH DISCHARGES INTO THE EXISTING STORMWATER SYSTEM ALONG THE RIGHT-OF-WAY OF US HWY 441. AREA (2): 20.07 ACRES OF RUNOFF WILL BE ATTENUATED BY BASIN No. (2) WHICH DISCHARGES INTO THE EXISTING WETLAND AT THE NORTHERN END OF THE PROJECT SITE. AREA (3): 16.38 ACRES OF RUNOFF WILL SHEET FLOW INTO THE EXISTING WETLAND AS IN EXISTING CONDITIONS.
- EXISTING AND FUTURE DRAINAGE PATTERNS ARE SHOWN ON THE DRAINAGE PLAN FOR PRE-DEVELOPMENT CONDITIONS AND POST-DEVELOPMENT CONDITIONS. OUTFALLS, AND STORMWATER BASINS ARE SHOWN IN THE DRAINAGE PLAN AND THE DETAIL PLAN.
- 4. SEQUENCE OF CONSTRUCTION:
- A. PRIOR TO CONSTRUCTION, SILT FENCING AND TREE PROTECTION BARRICADES SHALL BE INSTALLED AND ALL EXISTING DRAINAGE STRUCTURES SHALL BE PROTECTED IN ACCORDANCE WITH THE FDOT FLORIDA EROSION AND SEDIMENTATION CONTROL MANUAL
- B. THE CONSTRUCTION ENTRANCE(S) WILL BE STABILIZED TO MINIMIZE THE CREATION OF DUST AND OFF SITE TRACKING OF SEDIMENTS.
- C. THE SITE SHALL BE CLEARED AND GRUBBED OF UNDESIRABLE VEGETATION.
- D. THE UNDERGROUND UTILITIES AND STORMWATER PIPING WILL BE INSTALLED

AND CONNECTED TO EXISTING STRUCTURES.

- E. THE SITE WILL BE ROUGHLY GRADED. IF SUITABLE, THE EXCAVATED MATERIAL MAY BE USED AS FILL FOR ON-SITE GRADING. THE ROADWAYS SHALL BE GRADED. (THE BASIN AREA SHALL BE STABILIZED AS SPECIFIED IN THE PLANS.)
- F. ROADWAYS AND PARKING LOTS WILL BE COMPACTED AND A LIMEROCK BASE WILL BE ESTABLISHED FOLLOWED BY AN OVERLAY OF ASPHALTIC CONCRETE. BUILDINGS SHALL BE CONSTRUCTED.
- G. UPON SIGNIFICANT COMPLETION OF CONSTRUCTION, THE STORMWATER SYSTEM SHALL BE FLUSHED OUT TO REMOVE ACCUMULATED DEBRIS AND
- H. STORMWATER BASIN(S) WILL BE SCRAPED CLEAN OF ACCUMULATED
- I. ALL DISTURBED AREAS WITHIN THE CONSTRUCTION AREA SHALL BE COMPLETELY GRASSED AND/OR LANDSCAPED. EVIDENCE OF GROWTH MUST BE PRESENT PRIOR TO REMOVAL OF SILT FENCING AND OTHER EROSION

III. CONTROLS:

THE CONTROLS SHALL BE IMPLEMENTED AND MAINTAINED DURING THE ENTIRE CONSTRUCTION OF THE PROJECT. IF SITE CONDITIONS ARE SUCH THAT ADDITIONAL CONTROL MEASURES ARE REQUIRED THAN WHAT IS SPECIFIED IN THE EROSION AND SEDIMENTATION CONTROL PLAN, THEN THE CONTRACTOR SHALL IMPLEMENT ADDITIONAL BEST MANAGEMENT PRACTICES NECESSARY.

- THE CONSTRUCTION ACCESS SHALL BE STABILIZED WITH GRAVEL AND TEMPORARY VEGETATION TO PREVENT SILT LEAVING THE SITE.
- 2. TREE BARRICADES SHALL BE IMPLEMENTED BEFORE CLEARING AND GRUBBING OF ANY OF THE WORK AREAS.
- 3. BEFORE CLEARING, SILT FENCES SHALL BE INSTALLED AROUND THE PERIMETER OF THE CONSTRUCTION AND AROUND THE WETLAND(S) AND/OR BASIN(S) AS SHOWN IN THE PLANS. ALL EXISTING STORM DRAINAGE SWALES AND INLETS SHALL BE PROTECTED PER THE FDOT FLORIDA EROSION AND SEDIMENTATION
- 4. AFTER CLEARING BUT BEFORE EXCAVATION AND GRADING, TEMPORARY BERMS AND SWALES SHALL BE CONSTRUCTED AS REQUIRED TO DIVERT THE FLOW INTO THE CORRESPONDING STORMWATER BASIN.
- 5. ALL BASIN AREA SHALL BE PROTECTED AS INDICATED ON THE PLANS.
- THE STORMWATER BASINS SHALL BE ROUGH GRADED TO WITHIN 6" OF THE DESIGNED BASIN BOTTOM. THE BASIN SIDE SLOPES SHALL BE STABILIZED AS SHOWN IN THE PLANS BY SEEDING, MULCHING AND/OR SODDING TO PREVENT EXCESSIVE FROSION.
- DURING CONSTRUCTION OF PAVING AND BUILDINGS, EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED AS REQUIRED.
- 8. ALL DISTURBED AREAS WITHIN THE CONSTRUCTION SITE SHALL BE COMPLETELY LANDSCAPED AND/OR GRASSED. FINAL STABILIZATION (INCLUDING SEEDING, MULCHING, SODDING OR RIPRAP) SHALL BE INSTALLED AS REQUIRED. GRASS SEEDING RATES AND MIXTURES SHALL BE PER FDOT INDEX 104. EVIDENCE OF GROWTH MUST BE PRESENT PRIOR TO REMOVAL OF SILT FENCING AND OTHER EROSION CONTROL APPLICATIONS AND PRIOR TO FINAL RELEASE.

IV. EROSION AND SEDIMENTATION CONTROLS:

STABILIZATION PRACTICES

- 1. ALL ENTRANCES TO THE SITE SHALL BE STABILIZED BEFORE CONSTRUCTION AND FURTHER DISTURBANCE BEGINS. GRAVEL PAD SHALL PROVIDE STABILIZATION AND MINIMIZE THE AMOUNT OF SEDIMENT LEAVING THE SITE. MAINTENANCE OF THE ENTRANCE SHALL INCLUDE SWEEPING OF THE AREA ADJACENT TO THE ENTRANCE. STONE AND GRAVEL MIGHT NEED TO BE PERIODICALLY ADDED TO MAINTAIN THE EFFECTIVENESS OF THE ENTRANCE(S).
- 2. TREE BARRICADES SHALL BE INSTALLED AROUND THE TREES AS SHOWN IN THE DETAIL PLAN TO PROTECT THE EXISTING VEGETATION.
- 3. MULCH SHALL BE PLACED IN THE AREAS REQUIRED TO PREVENT EROSION FROM STORMWATER RUNOFF AND THE AREAS SHOWN ON THE PLANS. MULCH SHALL BE ANCHORED TO RESIST WIND DISPLACEMENT AND SHALL BE INSPECTED AFTER EVERY RAINSTORM TO IDENTIFY AREAS WHERE MULCH HAS BEEN WASHED OUT OR LOOSENED. THESE AREAS SHALL HAVE MULCH COVER
- 4. SEEDING SHALL BE STARTED AFTER GRADING HAS BEEN FINISHED ON THE AREAS SHOWN IN THE PLANS. SEEDED AREAS SHOULD BE INSPECTED FOR FAILURE TO ESTABLISH, AND NECESSARY REPAIRS AND RESEEDING SHOULD BE MADE AS SOON AS POSSIBLE. ADDITIONAL SEEDING AND MULCH MAY BE REQUIRED AS NECESSARY TO PREVENT EROSION DURING OR AFTER CONSTRUCTION HAS FINISHED.
- 5. SOD SHALL BE INSTALLED IN THE AREAS SHOWN IN THE PLANS. SOD SHALL BE PEGGED IF INSTALLED ON SLOPES GREATER THAN 3:1. SODDED AREAS SHALL BE MAINTAINED AND INSPECTED TO ENSURE SUCCESSFUL ESTABLISHMENT.

SEDIMENTATION PRACTICES

- 1. SILT FENCES SHALL BE INSTALLED IN THE AREAS SHOWN IN THE PLANS AND AS REQUIRED TO PREVENT SEDIMENT FROM LEAVING THE CONSTRUCTION AREA. SILT FENCES SHALL BE INSPECTED AFTER EACH RAINFALL EVENT TO ENSURE THAT THERE ARE NO GAPS OR TEARS, IF GAPS OR TEARS ARE FOUND THE FABRIC SHOULD BE REPAIRED OR REPLACED. SEDIMENT REMOVAL SHALL BE PART OF THE REGULAR MAINTENANCE. SILT FENCES SHALL REMAIN IN PLACE UNTIL CONSTRUCTION HAS FINISHED AND DISTURBED AREAS ARE PERMANENTLY
- 2. DIVERSION SWALES, IF REQUIRED, SHALL BE CONSTRUCTED BEFORE MAJOR LAND DISTURBANCE OF THE RECEIVING BASIN. DIVERSION SWALES SHALL BE STABILIZED AFTER CONSTRUCTION TO MAINTAIN ITS EFFICIENCY.
- 3. INLETS SHOULD BE TEMPORARILY PROTECTED TO PREVENT SEDIMENT ENTERING THE INLET. BARRIERS WILL CATCH SOIL, DEBRIS AND SEDIMENT AT THE ENTRANCE OF THE INLET.
- 4. OUTFALL STRUCTURES SHALL HAVE SILT FENCES TO PREVENT SILT FROM ENTERING THE STORMWATER BASINS AND SHALL BE STABILIZED AS REQUIRED TO PREVENT EROSION FROM WASHOUTS.

V. STORMWATER MANAGEMENT:

- 1. THE PROPOSED PROJECT OBTAINED AN ENVIRONMENTAL RESOURCE PERMIT FROM SUWANNEE RIVER WATER MANAGEMENT DISTRICT (SRWMD) FOR THE CONSTRUCTION AND OPERATION OF A STORMWATER TREATMENT SYSTEM AND CONTROLS. THE PROPOSED SYSTEM (AS SHOWN ON THE PLANS) INCLUDED THE USE OF THE BEST MANAGEMENT PRACTICES (BMP) CONSISTENT WITH THE APPLICABLE REQUIREMENTS OF RULE 40C-42 OF THE DISTRICT. THE OWNER AND/OR THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE OPERATION AND MAINTENANCE OF THE STORMWATER TREATMENT SYSTEM AND CONTROLS UNTIL CONSTRUCTION ACTIVITIES ARE COMPLETED AND FINAL STABILIZATION HAS BEEN ACCOMPLISHED. HOWEVER, THE OWNER AND/OR AN ENTITY SIMILAR TO A HOMEOWNERS ASSOCIATION SHALL BE RESPONSIBLE FOR THE OPERATION AND MAINTENANCE OF THE STORMWATER SYSTEM IN PERPETUITY, IN ACCORDANCE WITH THE REQUIREMENTS OF THE ENVIRONMENTAL RESOURCE PERMIT.
- 2. TO TREAT AND CONTROL THE STORMWATER PRODUCED BY THE PROPOSED DEVELOPMENT, THE PROJECT REQUIRES THE INSTALLATION AND CONSTRUCTION OF THE FOLLOWING BMP'S: 2 DRY RETENTION BASINS WITH ALL GRADING ASSOCIATED WITH THE CONSTRUCTION. THE BASIN SYSTEM HAS BEEN DESIGNED TO CONTAIN AND ATTENUATE THE STORMS AND DISCHARGE AT PRE-DEVELOPMENT CONDITIONS, WHILE PROVIDING TREATMENT TO THE RUNOFF AS REQUIRED BY THE DISTRICT AND STATE RULES USING THE GUIDELINES
- 3. AREA 1 WILL HAVE A DRY RETENTION BASIN THAT DISCHARGES TO THE EXISTING STORMWATER SYSTEM ALONG THE RIGHT-OF-WAY OF US HWY 441. AREA 2 WILL HAVE A DRY RETENTION BASIN THAT DISCHARGES TO THE

VI. CONTROLS FOR OTHER POTENTIAL POLLUTANTS:

- 1. WASTE DISPOSAL: NO SOLID MATERIALS, INCLUDING CONSTRUCTION MATERIALS, SHALL BE DISCHARGED TO SURFACE WATERS AND ARE NOT AUTHORIZED UNDER THE ISSUED ENVIRONMENTAL RESOURCE PERMIT.
- 2. THE USE OF GRAVEL AND CONTINUING SWEEPING ACTIVITIES AT THE ENTRANCE OF THE SITE WILL CONTROL THE TRACKING OF SEDIMENT AND DUST LEAVING
- 3. THE PROPOSED DEVELOPMENT WILL PROVIDE WATER AND SEWER SYSTEM BY CONNECTING INTO THE CENTRAL MUNICIPAL SYSTEM OF GAINESVILLE REGIONAL
- 4. ANY APPLICATION OF FERTILIZERS AND PESTICIDES NECESSARY TO ESTABLISH AND MAINTENANCE OF VEGETATION DURING CONSTRUCTION AND THROUGH PERPETUITY MAINTENANCE SHALL FOLLOW THE MANUFACTURERS RECOMMENDATIONS AND THE APPLICABLE RULES OF THE STATE OF FLORIDA.
- 5. ANY TOXIC MATERIALS REQUIRED DURING CONSTRUCTION SHALL BE PROPERLY STORED, DISPOSED OF AND CONTRACTOR AND/OR OWNER SHALL PROVIDE THE APPROPRIATE PERMITS FROM THE LOCAL OR STATE AGENCIES.

VII. APPROVED STATE OR LOCAL PLANS:

- 1. ALL THE SEDIMENT AND EROSION CONTROLS THAT ARE LISTED IN THE SITE PLAN AS APPROVED BY THE SJRWMD ARE INCLUDED IN THIS STORMWATER POLLUTION PREVENTION PLAN (SEE ITEM III AND IV).
- 2. THIS STORMWATER POLLUTION PREVENTION PLAN SHALL BE AMENDED IF REQUIRED BY ANY LOCAL OR STATE AGENCY OR AS REQUIRED BY UNFORESEEABLE CONDITIONS AND THE OWNER SHALL SUBMIT A RE-CERTIFICATION TO THE NPDES STATE OFFICE THAT THE PLAN HAS BEEN AMENDED TO ADDRESS THOSE CHANGES.

VIII. MAINTENANCE:

THE CONTRACTOR IS RESPONSIBLE FOR THE MAINTENANCE, INSPECTION SCHEDULE, AND REPAIRS OUTLINED IN THIS PLAN. MAINTENANCE SHALL CONTINUE THROUGHOUT THE PROJECT UNTIL WORK IS COMPLETE. THE CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES AFTER CONSTRUCTION IS COMPLETE.

IN ADDITION TO THE ITEMS MENTIONED IN THE PREVIOUS SECTIONS, THE CONTRACTOR SHALL INITIATE ANY REPAIRS WITHIN 24 HOURS OF BEING REPORTED. IN THE EVENT THAT THE BASINS DO NOT PERFORM PROPERLY OR IF A SINKHOLE DEVELOPS, THE PROJECT ENGINEER SHALL BE NOTIFIED TO ASSIST IN COORDINATING REMEDIAL ACTION.

- 1. MAINTENANCE WOULD BE DIVIDED IN ROUTINE MAINTENANCE AND REPAIR MAINTENANCE, ALL STORMWATER BMP'S SHOULD BE INSPECTED FOR CONTINUED EFFECTIVENESS AND STRUCTURAL INTEGRITY ON A REGULAR BASIS. THE SYSTEMS SHOULD BE CHECKED AFTER EACH STORM EVENT IN ADDITION TO REGULARLY SCHEDULED INSPECTIONS.
- 2. ROUTINE MAINTENANCE REQUIREMENTS SHOULD BE INCLUDED IN THE INSPECTOR CHECKLIST TO AID THE INSPECTOR IN DETERMINING WHETHER A BMP'S MAINTENANCE IS ADEQUATE OR NEEDS A REVISION. INSPECTORS SHALL KEEP RECORD OF MAINTENANCE, ROUTINE OR REPAIR, TO PROVIDE EVIDENCE OF AN EFFICIENT INSPECTION AND MAINTENANCE.
- 3. SIDE ENTRANCES: MAINTENANCE SHALL INCLUDE REPLACEMENT OF GRAVEL AND CLEANING THE SOIL THAT IS TRACKED OFFSITE FOR PROPER
- 4. TREE BARRICADES: MAINTENANCE SHALL INCLUDE INSPECTION OF MESH AND POSTS AND REPAIR OR REPLACEMENT OF DAMAGED VEGETATION.
- 5. SILT FENCES: MAINTENANCE SHALL INCLUDE SEDIMENT REMOVAL AND INSPECTION TO ENSURE PROPER ANCHORING AND THAT NO TEARING OR GAPS HAVE OCCURRED. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT HAS REACHED ONE-THIRD THE HEIGHT OF SILT FENCE.
- 6. DIVERSION SWALES: MAINTENANCE SHALL INCLUDE INSPECTION AFTER EVERY RAINFALL EVENT AND ONCE EVERY TWO WEEKS BEFORE FINAL STABILIZATION. THEY SHOULD BE CLEARED OF SEDIMENT AND MAINTAIN
- 7. TEMPORARY BERMS: MAINTENANCE SHALL INCLUDE REMOVAL OF DEBRIS. TRASH SEDIMENT AND LEAVES. SIDES OF THE BERM SHALL BE INSPECTED FOR EROSION AFTER EACH STORM EVENT.
- 8. MULCHING: ROUTINE MAINTENANCE SHALL INCLUDE REPLACEMENT PERIODICALLY.
- 9. SEEDING: ROUTINE MAINTENANCE SHALL INCLUDE RESEEDING OF AREAS
- 10. SODDING: ROUTINE MAINTENANCE SHALL INCLUDE WATERING AND MOWING. REPLACEMENT OF GRASS MAY BE NECESSARY IF COVER IS NOT FULLY
- 11. INLETS: ROUTINE MAINTENANCE SHALL INCLUDE INSPECTION AFTER EVERY STORM EVENT AND MIGHT INCLUDE REMOVAL OF ACCUMULATED SEDIMENT.
- 12. OUTFALL STRUCTURES: ROUTINE MAINTENANCE SHALL INCLUDE INSPECTION AFTER EVERY STORM EVENT TO ASSURE NO EROSION OR SCOUR HAS
- 13. DRY RETENTION BASINS: ROUTINE MAINTENANCE SHALL INCLUDE MONITORING FOR SEDIMENT ACCUMULATION, CLEAN AND REMOVE DEBRIS FROM INLETS AND OUTLETS, MOW SIDE SLOPES AND INSPECT FOR DAMAGE OF BERMS AND REPAIR UNDERCUT OR ERODED AREAS AS NECESSARY.
- 14. WET DETENTION BASINS: ROUTINE MAINTENANCE SHALL INCLUDE MONITORING FOR SEDIMENT ACCUMULATION, CLEAN AND REMOVE DEBRIS FROM INLETS AND OUTLETS, MOW SIDE SLOPES AND INSPECT FOR DAMAGE OF BERMS AND REPAIR UNDERCUT OR ERODED AREAS AS NECESSARY.

OWNER: _

Date of

Inspection

CONDITION CODE:

CONTROL TYPE CODES

Silt Fence

5. Check dam

. Swale

Name

Earth dikes

. Sediment Trap

7. Subsurface drain

INSPECTOR INFORMATION:

and imprisonment for knowing violations.

8. Pipe slope drain

9. Level spreaders

PROJECT NAME: SAN FELASCO TECH CITY

Location

G = Good

. Structural diversion | 12. Vegetative preservation area

C = Needs to be cleaned

10. Storm drain inlet protection

11. Vegetative buffer strip

13. Retention Pond

15. Perimeter ditch

16. Curb and gutter

17. Paved road surface

18. Rock outlet protection

CONSTRUCTION MANAGER:

IX. INSPECTIONS:

- 1. THE OWNER AND /OR CONTRACTOR SHALL PROVIDE QUALIFIED PERSONNEL TO INSPECT ALL POINTS OF POTENTIAL DISCHARGE FROM THE PROJECT SITE FOR DISTURBED AREAS, THE EROSION AND SEDIMENTATION CONTROLS AND BMP'S AS LISTED IN THIS PLAN. THE INSPECTION SHALL BE PERFORMED DURING CONSTRUCTION AND BEFORE FINAL STABILIZATION, ONCE EVERY SEVEN-CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM THAT IS GREATER THAN 0.50 INCHES. AFTER FINAL STABILIZATION AND BEFORE FINISH OF CONSTRUCTION THE INSPECTION SHALL BE CONDUCTED
- 2. THE CONTRACTOR SHALL INSTALL A RAIN GAUGE AT THE SITE TO MONITOR AND DOCUMENT RAINFALL EVENTS IN EXCESS OF 0.50 INCHES.
- 3. ALL DISTURBED AREAS AND AREAS USED FOR MATERIALS STORAGE SHALL BE INSPECTED FOR POLLUTANTS ENTERING THE STORMWATER SYSTEM. THE STORMWATER MANAGEMENT SYSTEM AND EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN SHALL BE INSPECTED TO ENSURE THEY ARE OPERATING CORRECTLY. LOCATIONS WHERE VEHICLES ENTER AND LEAVE THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFFSITE SEDIMENT
- 4. REPAIR OR MAINTENANCE NEEDED TO ASSURE PROPER OPERATION OF THE STORMWATER POLLUTION PREVENTION PLAN SHALL BE DONE IN A TIMELY MANNER BUT NO LATER THAN 7 CALENDAR DAYS FOLLOWING THE
- 5. A REPORT SHALL BE KEPT OF EACH INSPECTION FOR THREE YEARS AFTER FINAL STABILIZATION AND SHALL INCLUDE THE DATES OF EACH INSPECTION, THE SCOPE OF THE INSPECTION, MAJOR OBSERVATIONS, ANY REPAIR AND/OR MAINTENANCE REQUIRED AND ANY INCIDENT OF NON-COMPLIANCE. IF THE REPORT DOES NOT CONTAIN ANY INCIDENTS OF NON-COMPLIANCE, THE REPORT SHALL CONTAIN A CERTIFICATION THAT THE FACILITY HAS BEEN IN COMPLIANCE WITH THE STORMWATER POLLUTION PREVENTION PLAN AND THE NPDES PERMIT. THE REPORT SHALL INCLUDE THE NAME AND QUALIFICATIONS OF THE INSPECTOR AND SHALL BE SIGNED IN ACCORDANCE TO FDEP RULE 62-621.300. PART VII.C. A COPY OF THE CONSTRUCTION INSPECTION FORM IS INCLUDED ON THIS STORMWATER POLLUTION PREVENTION PLAN SHEET. A COPY SHALL BE RETAINED AT THE CONSTRUCTION SITE FROM THE DATE OF PROJECT INITIATION TO THE DATE OF FINAL STABILIZATION.

X. NON-STORMWATER DISCHARGES:

- THE FOLLOWING NON-STORMWATER DISCHARGES MIGHT BE COMBINED WITH STORMWATER AND WOULD BE AUTHORIZED AS PART OF THIS PERMIT: FIRE HYDRANT FLUSHING, CONTROL OF DUST, POTABLE WATER FLUSHING AND IRRIGATION DRAINAGE. BECAUSE OF THE NATURE OF THESE DISCHARGES, THE EROSION, STABILIZATION AND TREATMENT SYSTEMS TO BE IMPLEMENTED, AS PART OF THIS PLAN WOULD BE APPROPRIATE TO PREVENT AND TREAT ANY POLLUTION RELATED TO THESE NON-STORMWATER DISCHARGES.
- 2. DISCHARGES FROM DEWATERING ACTIVITIES ASSOCIATED WITH SITE CONSTRUCTION ARE NOT AUTHORIZED AND REQUIRED CONSTRUCTION OF TEMPORARY SEDIMENTATION BASINS AND USE OF APPROPRIATE FLOCCULATING AGENTS TO ENHANCE PARTICLE SEGREGATION AND SPEED UP SETTLING OF PARTICLES.

XI. CONTRACTORS:

1. ALL CONTRACTORS AND/OR SUBCONTRACTORS RESPONSIBLE FOR IMPLEMENTING THE PLAN SHALL SIGN THE CERTIFICATION STATEMENT BEFORE STARTING CONSTRUCTION ACTIVITIES OF THE PROJECT. THE CERTIFICATION MUST INCLUDE THE NAME AND TITLE OF THE PERSON PROVIDING THE SIGNATURE. THE NAME. ADDRESS AND TELEPHONE NUMBER OF THE CONTRACTING FIRM, THE ADDRESS OF THE SITE AND THE DATE THE CERTIFICATION IS MADE. THE OWNER SHALL KEEP THESE CERTIFICATIONS AS PART OF THIS POLLUTION PLAN. MULTIPLE COPIES OF THE CERTIFICATION STATEMENT MAY BE NECESSARY DEPENDING UPON THE NUMBER OF SUBCONTRACTORS ASSOCIATED WITH THE PROJECT.

Inspections must occur at least once a week and within 24 hours of the end of a storm event that is 0.50 inches or greater.

(see below)

CONTRACTOR: .

M = Marginal, needs maintenance or replacement soon O = Other

19. Reinforced soil retaining system | 28. Tree protection

P = Poor, needs immediate maintenance or replacement

FDEP NPDES STORMWATER IDENTIFICATION NO.: FLR10 _____

Observations or Corrective Action /

Other Remarks

29. Detention pond

30. Retention pond

32. Dam

34. Other

Date

33. Sand Bag

31. Waste disposal / housekeeping

STORMWATER POLLUTION PREVENTION PLAN INSPECTION REPORT FORM

20. Gabion

24. Mulch

27. Rip-rap

25. Hay Bales

26. Geotextile

The above signature also shall certify that this facility is in compliance with the Stormwater Pollution Prevention Plan and the State of Florida Generic

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons

who manage the system or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge

and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine

Permit for Stormwater Discharge from Large and Small Construction Activities if there are not any incidents of non compliance identified above.

21. Sediment Basin

22. Temporary seed / sod

Rain data | Type of control | Date installed | Current Condition |

14. Construction entrance stabilization | 23. Permanent seed / sod

Qualification

(see below)

/ modified

CERTIFICATION STATEMENT

"I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND AND SHALL COMPLY WITH THE TERMS AND CONDITIONS OF THE STATE OF FLORIDA GENERIC PERMIT FOR STORMWATER DISCHARGE FROM LARGE AND SMALL CONSTRUCTION ACTIVITIES AND THIS STORMWATER POLLUTION PREVENTION PLAN PREPARED THEREUNDER."

CONTRACTING FIRM:	
ADDRESS:	
CITY, STATE, ZIP COL	DE:
TELEPHONE:	
FAX:	
PROJECT NAME: SAN	FELASCO TECH CITY
PROJECT ADDRESS: 1	12000 BLOCK OF NW US HWY 441
CITY OF ALACHUA, F	LORIDA.
NAME:	SIGNATURE:
	DATE:

Inspected

Вy

GGO
engineers • surveyors • planner
EB 2389 2404 N.W. 43rd ST, GAINESVILLE, FLORIDA 32606-6

TEL. (352) 373-3541 FAX. (352) 373-7249

www.edafl.com mail@edafl.com

No.	Date	Comment

Professional Engineer of Record:
CEN CEN
No. 47311
*/
R STATE OF
Sergio J. Reyes, PAEA 47311
Engineer Certificate N


18-023 Project phase: CITY SUBMITTAL


Project title:

SAN FELASCO TECH CITY CITY OF ALACHUA, **FLORIDA**

STORMWATER POLLUTION PREVENTION PLAN


Designed:	SJR	Sheet No.:
Drawn:	MAB	
Checked:	TAR	C3
Date: 06	/25/18	






- 1. A FOUNDATION MAY BE REQUIRED IN VERY POOR SOIL CONDITIONS. FIELD DETERMINATION WILL BE PROVIDED BY INSPECTOR. TYPICAL FOUNDATION THICKNESS SHALL BE 12", BUT MAY VARY ACCORDING TO NATURAL MATERIAL.
- 2. BEDDING IS REQUIRED PRIMARILY TO BRING THE TRENCH BOTTOM UP TO GRADE. BEDDING MATERIALS SHALL PROVIDE A UNIFORM AND ADEQUATE LONGITUDINAL SUPPORT UNDER THE PIPE. IN DRY SOIL CONDITIONS CLASS II OR CLASS III MATERIAL SHALL BE HAND PLACED 4" TO 6", LIGHTLY COMPACTED, UNIFORM AND NOT FINER THAN THE FOUNDATION MATERIAL. IN WET SOIL CONDITIONS CLASS I, CLASS II OR CLASS III SHALL BE HAND PLACED, 4" TO 6", UNIFORM AND NOT FINER THAN THE FOUNDATION MATERIAL. WHEN UTILIZING CLASS I MATERIAL, SUFFICIENT AMOUNTS OF CLASS II OR CLASS III MATERIAL SHALL BE ADDED TO FILL ALL VOIDS CREATED BY THE CLASS I MATERIAL.
- 3. HAUNCHING MATERIAL SHALL BE HAND PLACED TO THE SPRINGLINE OF THE PIPE. CLASS II OR CLASS III MATERIAL SHALL BE CONSOLIDATED UNDER THE PIPE AND HAND TAMPED TO PROVIDE ADEQUATE SIDE SUPPORT.
- 4. INITIAL BACKFILL MATERIAL SHALL BE CLASS II OR CLASS III. IT SHALL BE HAND PLACED TO 12", ABOVE THE TOP OF THE PIPE. THE SOIL SHALL BE CONSOLIDATED BY HAND TAMPING OR WALKING THE SOIL IN PLACE.
- 5. FINAL BACKFILL MATERIAL MAY BE MACHINE PLACED. THE MATERIAL SHALL BE CLASS II OR CLASS III MATERIAL. CLASS IV MATERIAL MAY BE INSTALLED OUTSIDE OF THE ROADWAY. FINAL BACKFILL UNDER ROADWAYS MAY REQUIRE SPECIAL COMPACTION AND DENSITY TESTS.

BACKFILL REQUIREMENTS (WW-2.2)




WASTEWATER GRAVITY MAIN CONSTRUCTION




	MATERIALS
ITEM	DESCRIPTION
1	METER BOX 2" (BY CONTRACTOR, TO COA SPECS-DWF1300.12.1T
2	3" WATER MAIN (BY CONTRACTOR)
3	YOKE EXPANSION WHEEL
4	YOKE BAR - 2" (BY CONTRACTOR)
5	WATER METER - 2" (BY UTILITY COMPANY)
6	SCHEDULE 80 MALE ADAPTER (BY CONTRACTOR)
7	DUAL CHECK VALVE (BY CONTRACTOR)
8	TRACER WIRE COPPER BLUE INSULATED #10 AWG
9	CURB STOP (BY CONTRACTOR)
10	METER END CONNECTOR (BY CONTRACTOR)

WATER METER WITH YOKE BAR ASSEMBLY DETAIL




FIRE HYDRANT PERPENDICULAR TO THE MAIN



	MATER	IALS
ITEM	DESCRIPTION	DN
1	12", 16", 20", 24" X 6"	MJ ANCHORING TEE
2	6"	VALVE, GATE, MJ, RESILIENT WEDGE
3		VALVE BOX
4	6" X 16" or 72" (PER FIELD CONDITIONS)	ANCHORING COUPLING, MJ x MJ
5	6" X 45°	BEND, MJ × MJ
6	6" X VARIES	PIPE, D.I.P.
7	VISQUEEN	8 MILS THICKNESS (MIN.) or FELT 15 lb (MIN.)
8		EBAA MEGA LUG
9		TRACER WIRE
10	6"	CAP, C.I., MJ, EBAA MEGALUG
11	5/8" x 3/4"	RECLAIMED WATER METER BOX
12		CONCRETE, THRUST BLOCK (2500 psi)
13		UNDISTURBED EARTH

6' BLOW-OFF ASSEMBLY



NOTE: WHEN MANHOLE IS OUTSIDE PAVEMENT, THE RIM ELEVATION SHALL BE 6" ABOVE NATURAL GRADE. WITH FILL ADDED FOR A 10:1 SLOPE TO NATURAL GRADE.

1 MANHOLE RING & COVER 2 ECCENTRIC CONE		MATERIALS
	ITEM	DESCRIPTION
2 ECCENTRIC CONE	1	MANHOLE RING & COVER
	2	ECCENTRIC CONE

NOTE: IN LOCATIONS WHERE STORMWATER INFILTRATION MAY BE POSSIBLE, A MANHOLE PAN WILL BE REQUIRED.

MANHOLE OUTSIDE OF PAVEMENT

OF SLAB (MIN.)

MATERIALS

2 6" GATE VALVE, FL X FL (END CITY MAINTENANCE)

8 3/4" SHUTOFF VALVE AND DETECTION BYPASS METER

FINAL GRADE

7 6" BACKFLOW PREVENTOR (DOUBLE CHECK OR REDUCED PRESSURE)

13 6" FIRE LINE METER WITH STRAINER (UL LISTED AND FM APPROVED)

1. DETECTOR CHECK VALVE ASSEMBLY MAY NOT BE REQUIRED FOR ALL INSTALLATIONS.

2. BACKFLOW PREVENTER SHALL BE INSTALLED WITH A FREEZE PROTECTION BOX PER CITY OF ALACHUA STANDARDS.

6' FIRELINE CONNECTION WITH TURBINE METER AND **DOUBLE CHECK BACKFLOW PREVENTER ASSEMBLY**

N.T.S.

MATERIALS

3" x 4" LONG GALVINIZED NIPPLE

3" GATE VALVE, SQUARE NUT, RESILIENT WEDGE

DESCRIPTION

8" WATER MAIN

3" x 6" LONG PVC PIPE

VALVE BOX

5 6" DUCTILE IRON PIPE-FLANGE X P.E.

12 6" D.I. 90° BEND M.J. WITH EBAA MEGA LUG

6 6" OS & Y TYPE GATE VALVE

9 3/4" DETECTOR CHECK VALVE 10 6" CONCRETE SLAB (3500 PSI) SIZE VARIES

FIRE PROTECTION SYSTEM

TO BUILDING —/
FIRE PROTECTION SYSTEM

SIZE VARIES

TO DOMESTIC METER/SUPPLY

└D.I. TEE, M.J.

ITEM DESCRIPTION

1 6" FIRE MAIN

3 VALVE BOX, C.I.

11 NOT USED

4 6" BEND 90° FL X FL

LTHRUST BLOCK

GENERAL UTILITY NOTES


- CONTRACTOR IS RESPONSIBLE FOR PROTECTION AND VERIFICATION OF EXISTING UTILITIES. ANY EXISTING UTILITY TO BE MODIFIED SHALL BE COORDINATED WITH THE APPROPRIATE UTILITY PROVIDER.
- 2. WATER METER ASSEMBLIES SHALL BE INSTALLED BY CONTRACTOR.
- 3. ELECTRIC SERVICE TO BE COORDINATED WITH THE CITY OF ALACHUA PUBLIC SERVICES DEPARTMENT.
- 4. UTILITY INSTALLATION SHALL NOT TAKE PLACE WITHIN TREE BARRICADE AREA AS SHOWN ON THE PAVING, GRADING AND DRAINAGE PLAN.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DISPOSAL OF UNSUITABLE MATERIALS OFF-SITE AND FURNISH APPROVED MATERIAL PER CITY OF GAINESVILLE FOR SANITARY SEWER LINES BACKFILL AT NO ADDITIONAL COST TO THE OWNER. THE CONTRACTOR MAY DISPOSE OF UNSUITABLE MATERIAL ON-SITE BY APPROVAL OF THE OWNER.
- 6. NO PERMANENT STRUCTURE SHALL BE CONSTRUCTED WITHIN 10 FEET OF ANY WATER LINE OR 15 FEET OF ANY SEWER LINE.
- CONTRACTOR SHALL PROTECT LANDSCAPE AND ANY DISTURBED AREAS SHALL BE RESTORED AS EXISTING.

engineers • surveyors • planners

2404 N.W. 43rd ST, GAINESVILLE, FLORIDA 32606-6602

TEL. (352) 373-3541 FAX. (352) 373-7249

www.edafl.com mail@edafl.com



BEARING AREA MATERIALS DESCRIPTION FIRE HYDRANT ANCHORING COUPLING VALVE BOX 4 GATE VALVE 5 ANCHORING TEE 6 CONCRETE THRUST BLOCK (2500 psi) 7 GRAVEL DRAIN BED 8 TRACER WIRE 9 ANCHORING, 90° BEND. M.J.

1. A NONPOROUS MATERIAL 8 MILS (MIN.) VISQUEEN OR 15 Ib FELT SHOULD BE PLACED BETWEEN THE CONCRETE AND ENTIRE FITTINGS.

No.	Date	Comment

SCALES: AS SHOWN

Professional Engineer of Record: STATE OF Sergio J. Reyes, P.E. 47311

	Engineer Certificate No.
Project	
	18-023
Project	phase:
	CITY SUBMITTAL
Project	title:

SAN FELASCO TECH CITY CITY OF ALACHUA, **FLORIDA**

heet	title:	

Designed: SJR Sheet No.

	G G	S.1.552 1.511
rawn:	MAB	
hecked:	TAR	$\mid C4.10$
ate: 06,	/25/18	

UTILITY DETAILS

POTABLE WATER	SERVICE DETAIL	. VIA TAPPING SADD	LE

MATERIALS

TRACER WIRE, BLUE, # 10 AWG

8" x 3" SERVICE SADDLE

3" PVC WATER LINE

DESCRIPTION

BOUNDARY AND TOPOGRAPHIC SURVEY

SECTION 20, TOWNSHIP 8 SOUTH, RANGE 19 EAST, CITY OF ALACHUA, ALACHUA COUNTY, FLORIDA MITCH GLAESER

LEGAL DESCRIPTION: (PER OFFICIAL RECORDS BOOK 3842, PAGE 1386)

A parcel of land located in Section 20, Township 8 South, Range 19 East, Alachua County, Florida and being more particularly described as follows:

Commence at a found iron pin marking the Southeast corner of Section 20, Township 8 South, Range 19 East, Alachua County, Florida; thence West a distance of 1313.40 feet to a point; thence North a distance of 218.99 feet to a found 3/4" iron pin marking a point on the North right-of-way line of U. S. Highway No. 441 (200 foot right-of-way); thence along said North right-of-way line; North 72 deg. 51 min. 49 sec. West a distance of 171.11 feet to a found 5/8 inch iron pin (Florida D.O.T.) marking the point of curvature of a curve concave to the Northeast, having a delta of 06 deg. 52 min. 05 sec., a radius of 11424.66 feet and a chord bearing North 69 deg. 24 min. 13 sec. West, 1368.62 feet; thence along the arc of said curve a distance of 1369.44 feet to a found 6" x 6" concrete monument (Florida D.O.T.); thence North 65 deg. 59 min. 42 sec. West a distance of 1385.74 feet to a found 5/8 inch rebar and cap (#3524); thence departing said North right—of—way line, North 22 deg. 09 min. 10 sec. East a distance of 158.44 feet to a found 5/8 inch rebar and cap (#3524); thence North 66 deg. 13 min. 12 sec. West a distance of 229.98 feet to a found 5/8 inch rebar and cap (#3524); thence North 01 deg. 33 min. 26 sec. East a distance of 169.02 feet to a found 4" x 4" concrete monument (PLS #940) marking the Point of Beginning; thence North 23 deg. 50 min. 23 sec. East a distance of 2014.63 feet to a set 5/8 inch rebar and cap (#3524) marking a point on the South right-of-way line of Seaboard Coast Line Railroad(200 foot right-of-way); thence along said South right-of-way line of Seaboard Coast Line Railroad, North 58 deg. 44 min. 53 sec. West a distance of 624.24 feet to a found 5/8 inch rebar and cap (#3524); thence departing said South right-of-way line, South 00 deg. 37 min. 49 sec. East a distance of 70.66 feet to a found 5/8 inch rebar and cap (#3524); thence North 58 deg. 44 min. 53 sec. West a distance of 547.93 feet to a found 5/8 inch rebar and cap (#3524) marking the point of curvature of a curve concave to the Southwest, having a delta of 10 deg. 00 min. 21 sec., a radius of 2712.57 feet and a chord bearing North 63 deg. 45 min. 03 sec. West, 473.11 feet thence along the arc of said curve a distance of 473.71 feet to a found 5/8 inch rebar and cap (#3524); thence South 00 deg. 08 min. 45 sec. West a distance of 2657.79 feet to a found 5/8 inch rebar and cap (#3524) marking a point on said North right-of-way line of U. S. Highway No. 441; thence along said North right-of-way line, South 66 deg 00 min. 09 sec. East a distance of 209.40 feet to a found 4" x 4" concrete monument; thence departing said North right-of-way line, North 01 deg. 07 min. 22 sec. East a distance of 340.98 feet to a found 4" x 4" concrete monument; thence South 65 deg. 57 min. 03 sec. East a distance of 460.08 feet to the Point of Beginning.

Together with a perpetual, non-exclusive and unrestricted easement over, under and across the following two parcels of real property.

Easement Parcel #1

Commence at the Half Mile corner on the North line of Section 19, Township 8 South, Range 19 East, and run South 499.11 feet to the Southerly right—of-way line of the Seaboard Coastline Railroad; thence run, South 81 deg. 45' 10" East along said Southerly right—of—way line 2797.03 feet to the P.C. of a curve concave to the Southwest and having a radius at 2764.93 feet; thence run Southeasterly along said Southerly right—of—way line an arc distance of 498.99 feet to a concrete monument at the Northwest corner of General Electric Co. property, said point being the P.O.B.; thence continue Southeasterly along said right—of—way an arc distance of 31.68 feet and a chord bearing and distance of South 71 deg. 06' 52" East 31.68 feet; thence run South 00 deg. 08'45" West parallel with and 30 feet from the West line of said General Electric Co. property, 2718.20 feet to the Northerly right—of-way line of U.S. Highway No. 441 (State Road No. 25); thence run North 66 deg. 00' 06" West along said right-of-way line 32.8 feet to the southwest corner of said property, being a concrete monument; thence run North 00 deg. 08' 45" East along the West line of said property 2715.11 feet to the P.O.B., being and lying in Section 20, Township 8 South, Range 19 East, Alachua county, Florida.

Easement Parcel #2

R=11424.66'(R) A=1369.44'(R)

Commence at the Half Mile corner on the North line of Section 19, Township 8 South, Range 19 East and run South 499.11 feet to the Southerly right-of-way line of the Seaboard Coastline Railroad; thence run South 81 deg. 45' 10" East along said Southerly right—of—way line 2797.03 feet to the P.C. of a curve concave to the Southwest and having a radius of 2764.93 feet; thence run Southeasterly along said Southerly right—of—way line an arc distance of 498.99 feet to a concrete monument at the Northwest corner of General Electric Co. property; thence continue Southeasterly along said Southerly right—of—way line an arc distance of 31.68 feet and a chord bearing and distance of South 71 deg. 06' 52" East 31.68 feet to the P.O.B.; thence continue Southeasterly along said Southerly right—of—way line an arc distance of 582.25 feet and a chord bearing and distance of South 64 deg. 45' 10" East 581.17 feet to the P.T. of said curve; thence continue along said right-of-way line South 58 deg. 43' 12" East 510.61 feet; thence run South 00 deg. 37' 54" East 70.68 feet; thence run North 58 deg. 43' 12" West parallel with and 60 feet from the Southerly right-of-way line of said railroad, 547.97 feet to the P.C. of a curve concave to the Southwest and having a radius of 2704.93 feet; thence run Northwesterly along said curve an arc distance of 484.91 feet and a chord bearing and distance of North 63 deg. 51' 21" West 484.26 feet; thence run South 00 deg. 08' 45" West parallel with and 90 feet East of the West line of said G. E. property 2659.10 feet to the North right—of—way line of U.S. Highway No. 441 (State Road No. 25); thence run North 66 deg. 00'06" West along said right-of-way line 65.6 feet; thence run North 00 deg. 08' 45" East 2718.2 feet to the P.O.B. Being and lying in Section 20, Township 8 South, Range 19 East, Alachua County, Florida.

NOTES:

- 1) THE ELEVATIONS SHOWN HEREON ARE NAVD 1988 DATUM. ELEVATIONS SHOWN HEREON WERE BASED ON AN ELEVATION OF 157.834 FEET (NGVD 1929 DATUM) ON FLORIDA DEPARTMENT OF TRANSPORTATION BENCHMARK "BM4", BEING A CONCRETE MONUMENT WITH BRASS DISK STAMPED "2602006 BM-26-97-A-0" AT THE APPROXIMATE SOUTH RIGHT-OF-WAY LINE OF US 441 AND +/- 1,200 SOUTHEAST OF THE CENTERLINE OF SW 89TH ST. FOR THE PURPOSES OF THIS SURVEY, THIS ELEVATION WAS CONVERTED TO 157.04 FEET (NAVD 1988 DATUM) WITH CORPSCON v6.0.1, U.S. ARMY CORPS OF ENGINEERS.
- 2) BEARINGS AS SHOWN HEREON ARE BASED ON STATE PLANE COORDINATES (NORTH AMERICAN DATUM OF 1983, FLORIDA NORTH ZONE) WITH A MEASURED BEARING OF SOUTH 67'01'06" EAST ON THE NORTH RIGHT OF WAY LINE OF STATE ROAD No.s 20 & 25, U.S. HIGHWAY No. 441.
- 3) ONLY TREES 10" IN DIAMETER AND GREATER WERE LOCATED AS A PART OF THIS SURVEY. THE SCIENTIFIC NAMES SHOWN HEREON ARE TO THE BEST ABILITY OF THIS SURVEYOR, BUT THIS SURVEYOR DOES NOT PURPORT TO BE A CERTIFIED ARBORIST. THE LOCATION OF THE TREES SHOWN HEREON IS THE APPROXIMATE CENTER OF THE TREE AT GROUND LEVEL AND THE DIAMETER WAS MEASURED AT BREAST HEIGHT — THE EXTENT OF THE TREE CANOPY OR ROOT SYSTEM WAS NOT DETERMINED BY THIS SURVEYOR. IF THE LOCATION OF TREES IN RELATION TO NEARBY PROPERTY LINES IS CRITICAL A MORE DETAILED SURVEY MAY BE REQUIRED.
- 4) THIS SURVEY CONSISTS OF 12 SHEETS AND IS NOT VALID WITHOUT ALL SHEETS.
- 5) NO SEARCH OF THE PUBLIC RECORDS WAS MADE BY THE SURVEYOR, THEREFORE, THERE MAY BE RESTRICTIONS OTHER THAN THOSE SHOWN HEREON WHICH MAY BE FOUND IN THE PUBLIC RECORDS OF ALACHUA COUNTY, FLORIDA. EASEMENTS AND BUILDING SETBACK REQUIREMENTS, OTHER THAN THOSE SHOWN, WERE NOT PROVIDED
- 6) THE WETLAND FLAGS SHOWN HEREON WERE PLACED BY PETE WALLACE OF ECOSYSTEM RESEARCH CORPORATION (386-462-5005) ON OR AROUND FEBRUARY 10, 2018. THIS SURVEYOR IS NOT A WETLANDS DELINEATOR.
- 7) PARCELS 1 AND 2 SHOWN HEREON WERE DEDICATED BY EASEMENT AND ROADWAY AGREEMENT RECORDED IN O.R. 1558, PAGE 1383 AND ACKNOWLEDGED BY AGREEMENTS RECORDED IN O.R. 4290, PAGE 2224, O.R. 4290, PAGE 2229, AND O.R. 4290, PAGE 2234 ALL OF THE PUBLIC RECORDS OF ALACHUA COUNTY, FLORIDA.

UTILITY LOCATION NOTE:

THE LOCATIONS OF UNDERGROUND UTILITIES SHOWN WERE BASED ON ABOVE GROUND FIXTURES, UTILITY COMPANY MAPS AVAILABLE TO THE SURVEYOR, AND ELECTRONIC DETECTION METHODS. UNLESS NOTED OTHERWISE ON THE GRAPHIC PORTION OF THIS SURVEY, NO UTILITIES WERE UNCOVERED TO VERIFY THEIR LOCATION.

NO GUARANTEE IS EITHER EXPRESSED OR IMPLIED BY THE SURVEYOR THAT THE LOCATIONS SHOWN REPRESENT THE ACTUAL LOCATIONS OF THOSE UTILITIES, THE UTILITY TYPE, OR THAT NO OTHER UTILITIES EXIST ON THE SITE. PRIOR TO THE DESIGN OF UTILITY CONNECTIONS, THE PROPOSED CONNECTION POINTS SHOULD BE EXCAVATED AS NECESSARY TO CONFIRM THEIR EXACT LOCATION, DEPTH AND CHARACTERISTICS.

IN ACCORDANCE WITH FLORIDA STATUTE CHAPTER 556, PRIOR TO ANY EXCAVATION, THE EXCAVATOR SHALL CONTACT SUNSHINE STATE ONE CALL OF FLORIDA AT 1-800-432-4770.

LEGEND OF SYMBOLS & ABBREVIATIONS:

cmp = CORRUGATED METAL PIPE CONC = CONCRETE D = DELTA (CENTRAL) ANGLE R = RADIUSA = ARC= TANGENT CB = CHORD BEARING CD = CHORD DISTANCE DIP = DUCTILE IRON PIPE EJB = ELECTRICAL JUNCTION BOX ELEV = ELEVATION FOCJB = FIBER OPTIC CABLE JUNCTION BOX ID. = IDENTIFICATION inv = INVERT (M) = MEASURED DIMENSION (R) = RECORD DIMENSION M.E.S. = MITERED END SECTION No. = NUMBER O.R. = OFFICIAL RECORDS BOOK PGS. = PAGES

RCP = REINFORCED CONCRETE PIPE R/W = RIGHT OF WAYSECTION 20-8-19 = SECTION 20, TOWNSHIP 8 SOUTH, RANGE 19 EAST

= FOUND REBAR & CAP (size, ID) \Diamond MBOX = MAIL BOX OPP = POWER POLE


OTP = TELEPHONE POLE TTELPED = TELEPHONE PEDESTAL TELEPHONE LINE MARKER TCTVPED = CABLE TELEVISION PEDESTAL \triangle wf(id) = WETLANDS FLAG (ID) = ELEVATION CONTOUR LINE -x \times = FENCE LINE — OHPL = OVERHEAD POWER LINE — OHTL = OVERHEAD TELEPHONE LINE --FOG--- FIBER OPTIC CABLE LINE

--FM--- = SANITARY SEWER FORCE MAIN-- USE -- = UNDERGROUND ELECTRIC LINE -- GAS--- UNDERGROUND GAS LINE --₩6∓--- UNDERGROUND TELEPHONE LINE -- USTY -- = UNDERGROUND CABLE TELEVISION LINE -- RWL--- = UNDERGROUND RECLAIMED WATER LINE

(6" PVC) = SIZE AND/OR MATERIAL AS PROVIDED BY UTILITY COMPANY = SPOT ELEVATION

F.D.O.T. = FLORIDA DEPARTMENT OF TRANSPORTATION PVC = POLY-VINYL CHLORIDE ANCH ← = GUY ANCHOR ♦ FOCMRK = FIBER OPTIC CABLE MARKER ■ = FOUND CONCRETE MONUMENT (size, ID)

---₩--- UNDERGROUND WATER LINE



SHEET 2 OF 12

SHEET 4 OF 12\

SHEET 6 OF 12

55.44 ACRES±

SHEET 3 OF 12

SHEET 5 OF 12

SHEET 7 OF 12

TREE LEGEND: ONLY TREES WITH A DIAMETER 10" AND GREATER WERE LOCATED FOR THIS SURVEY. (DIAMETER MEASURED 4.5' ABOVE GRADE) SIZE/COMMON NAME Genus species = 23" SOUTHERN REDCEDAR Juniperus silicicola = 25" BLACK CHERRY *Prunus serotina* = 17" LAUREL OAK Quercus hemisphaerica = 15" LIVE OAK Quercus virginiana lo15 = 12" PALM Sabal palmetto

= 12" WATER OAK Quercus nigra

= 16" PINE Pinus sp.

= 12" UNIDENTIFIED TREE

pi16

∘ tree12

WEST 1313.40'(R)

POINT OF COMMENCEMENT
SE CORNER 20-8-19

OF PRACTICE AS S AND MAPPERS IN SECTION 472.027 (IDITIONS AS OF.....

V-001

Sheet No.:



